

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

5. LEASE DESIGNATION AND SERIAL NO.  
UTU-73075

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

6. IF INDIAN, ALLOTTEE OR TRIBE NAME  
N/A

1a. TYPE OF WORK

DRILL ☒

DEEPEN ☐

7. UNIT AGREEMENT NAME

Drunkards Wash UTU-67921X

b. TYPE OF WELL

OIL  
WELL ☐

GAS  
WELL ☒ OTHER

SINGLE  
ZONE ☒

MULTIPLE  
ZONE ☐

8. FARM OR LEASE NAME, WELL NO.

USA 29-455

2. NAME OF OPERATOR

RIVER GAS CORPORATION

9. API WELL NO.

3. ADDRESS AND TELEPHONE NO.

6825 S. 5300 W. P.O. Box 851 Price, Utah 84501 (435) 613-9777

10. FIELD AND POOL, OR WILDCAT

Drunkards Wash Undesignated

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. \*)

At surface 940' FNL, 789' FWL

4371643 N

514538 E

At proposed prod. zone

11. SEC. T. R. M. OR BLK.

AND SURVEY OR AREA  
NW/4, NW/4, Sec. 29, T15S,  
R10E, SLB&M

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE\*

7.1 miles southwest of Price, Utah.

12. COUNTY OR PARISH

Carbon

13. STATE

15. DISTANCE FROM PROPOSED\*  
LOCATION TO NEAREST  
PROPERTY OR LEASE LINE, FT.  
(Also to nearest drig. unit line, if any)

539'

16. NO. OF ACRES IN LEASE

2232.19 Acres

17. NO. OF ACRES ASSIGNED  
TO THIS WELL

160 acres

18. DISTANCE FROM PROPOSED  
LOCATION TO NEAREST WELL,  
DRILLING, COMPLETED, OR  
APPLIED FOR, ON THIS LEASE, FT.

2250'

19. PROPOSED DEPTH

1750'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5718' GR

22. APPROX. DATE WORK WILL START\*

April 2001

23. PROPOSED CASING AND CEMENTING PROGRAM

| SIZE OF HOLE | GRADE, SIZE OF CASING | WEIGHT PER FOOT | SETTING DEPTH | QUANTITY OF CEMENT  |
|--------------|-----------------------|-----------------|---------------|---|
| 14"          | 12-3/4"               | Conductor       | 40'           |   |
| 11"          | J-55 8-5/8"           | 24 #/ft         | 175'          | 68 sks G+2% CaCl + 1/4# per sack flocl                              |
| 7-7/8"       | N-80 5-1/2"           | 17 #/ft         | 1740'         | 117 sks 50/50 POZ +8%gel+2%CaCl+10%extender. 97 sks "G" thixotropic |

DEC 11 1990

ORIGINAL

CONFIDENTIAL

Federal Approval of this  
Action is Necessary

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

*Jan Seibert*

TITLE

Permitting Specialist

DATE 12/7/00

(This space for Federal or State office use)

PERMIT NO.

43-007-30507

APPROVAL DATE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY

*Bradley G. Hill*

TITLE

BRADLEY G. HILL  
RECLAMATION SPECIALIST III


DATE

1/9/01

\*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency or the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

# Range 10 East



## Location

The Bearings Indicated are per the recorded plat obtained from the U.S. Land Office. The well location was determined using a Trimble 4400 GPS Unit. UTM Coordinates listed are NAD27 based, Zone 12 North and in Meters.

## Basis Of Elevation:


Basis of Elevation of 5612' as indicated in the NE Corner of Section 20, Township 15 South, Range 10 East, Salt Lake Base and Meridian, as shown on the Poison Spring Bench Quadrangle 7.5 Minute Series Map.

## Description of Well Point

Proposed Drill Hole located in the NW 1/4 NW 1/4 of Section 29; being 939.71' South and 788.96' East from the NW Corner of Section 29, T15S, R10E, Salt Lake Base & Meridian.

## Surveyor's Certificate:

I, John S. Huefner, a Registered Licensed Land Surveyor, holding Certificate #144842, State of Utah, do hereby certify that the information on this drawing is a true and accurate survey of the land, and was conducted under my personal supervision, as shown hereon.




## LEGEND:

- Drill Hole Location
- ⊕ Found Section Corner Monumented w/ Brass Cap unless indicated otherwise.
- Section Corner searched for but not found



## SCALE:



DRAWN BY:  
**P. BOYLEN**

CHECKED BY:  
**J.S.H.**

DATE:  
**11/30/00**

SCALE:  
**1"=1000'**

JOB NO.  
**644**

DRAWING NO.

**A-1**

SHEET 1 OF 4



3266 South 125 West  
Price, Utah 84501  
(801) 637-9300  
FAX (801) 637-2833

Services

**River Gas Corporation**

Well# 29-455

Section 29, T15S, R10E, S.L.B.&M.  
Carbon County, Utah



RIVER GAS CORPORATION

UTAH OPERATIONS  
6825 South 5300 West  
P.O. Box 851  
Price, Utah 84501  
Bus. (435) 613-9777  
FAX (435) 613-9782

December 7, 2000

Ms. Lisha Cordova  
State of Utah  
Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
SLC, Utah 84114-5801

RE: Application for Permit to Drill-  
USA 29-455, NW1/4 NW1/4 Sec.29  
T15S, R10E, SLB & M, Carbon County, Utah

Dear Ms. Cordova:

Enclosed is the original of the *Application for Permit to Drill* (APD). Included with the APD is the following information:

Exhibit "A"- Survey Plat of the Proposed Well Site;

Exhibit "B" - Proposed Location Map with Pipeline, Power, and Road Access;

Exhibit "C" - Drilling Site Layout;

Exhibit "D" - Drilling Information

Exhibit "E" - Multipoint Surface Use Plan

Exhibit "F" - Typical Road Cross-section;

Exhibit "G" - BOP Diagram;

Exhibit "H" - Typical Wellhead Manifold;

Exhibit "I" - Evidence of Bond;

ORIGINAL

CONFIDENTIAL

RECEIVED

DEC 11 2000

DIVISION OF  
OIL, GAS AND MINING

Ms. Lisha Cordova, DOGM  
Page Two  
December 7, 2000

This well is located more than 460' from the exterior boundary of the Drunkards Wash Federal Unit. Due to topographical constraints, however, the proposed location, 939.7' FNL and 788.96' FEL, is outside of the "spacing window" specified by Cause No. 137-2(B) and will be an exception location under Utah Administrative Code Rule R649-3-3-1.3. For this well location, as shown on the APD map 1 of 4, River Gas Corp. is the only "owner" of record for the offset drilling units in the SW1/4 of Section 20, NE1/4 Section 30 and SE1/4 of section 19. Therefore, the requirements for approval of an exception location should be satisfied as required under Utah Administrative Code Rule R649-3-3.

Thank you very much for your timely consideration of this application. Please feel free to contact me if you have any questions.

Sincerely,

A handwritten signature in cursive script, reading "Jean Semborski".

Jean Semborski  
Permitting Specialist

cc: RGC Well File

Bureau of Land Management  
Moab District  
Application for Permit to Drill  
On-Site Inspection Checklist

Company River Gas Corporation Well No. USA 29-455  
Location: Sec. 29, T 15 S, R 10E, Lease No. UTU-73075  
On-Site Inspection Date: 11/7/00

All operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, the approved plan of operations and the conditions of approval. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

A. DRILLING PROGRAM

1. Surface Formation and Estimated Formation Tops:  
Surface formation: Upper Mancos Shale  
Estimated top of Ferron Formation: 1180' TD=1750'
2. Estimated Depth at Which Oil, Gas, Water or Other Mineral Bearing Zones are Expected to be Encountered

| <u>Formation</u> | <u>Depth</u> |
|------------------|--------------|
|------------------|--------------|

|   |  |
|---|--|
| Expected Oil Zones: none                                      |  |
| Expected Gas Zones: Ferron Coal Interval: <u>1180' -1320'</u> |  |
| Expected Water Zones: <u>1180'-1320'</u>                      |  |
| Expected Mineral Zones: none                                  |  |

All fresh water and prospectively valuable minerals encountered during drilling will be recorded by depth and will be cased and cemented. When possible, water flow rates will be measured and samples will be taken and analyzed. All oil and gas shows will be tested to determine commercial potential.

3. Pressure Control Equipment- include schematics of the BOP and choke manifold, and describe testing procedures: Quick Test is contracted to test the manifold, blind rams, and B.O.P to 2000 psi. Surface casing is tested to 1 psi/ft. See attachment.

BOP systems will be consistent with API RP 53 and Onshore Oil and Gas Order No. 2. Pressure tests of the surface casing and all BOP equipment potentially subject to pressure will be conducted before drilling the surface casing shoe. Blowout preventer controls will be installed prior to drilling the surface casing shoe and will remain in use until the well is completed or abandoned. Ram preventers shall be inspected and operated each trip (no more than once a day is necessary), and annular preventers shall be inspected and operated weekly to ensure good mechanical working order. These inspections shall be recorded in the drilling log and in the daily drilling report.

4. Casing Program and Auxiliary Equipment - include casing size, weight, grade, thread and

coupling, setting depth and condition (new or acceptably reconditioned): Approximately 1740' of 5-1/2", N-80 17#/ft production casing will be installed 10% of the above setting depth will be 8-5/8", 24#/ft. J-55 surface casing.

5. Cement-include the cement type, density, yield, additives and amount used in setting each casing string. Also include the anticipated cement fill-up. If stage cementing, describe techniques: See cement design.
6. Mud Program and Circulating Medium- include mud components and weights. When air drilling, also include: length and location of blooie line; description of the auto ignitor; description of the deduster equipment; and amounts, types and characteristics of stand-by mud: Hole will be drilled with air.
7. Coring, Logging and Testing Program: Bulk Density, Gamma, Neutron Density, Resistivity and Caliper logs will be run.  
Initial opening of drill stem test tools will be restricted to daylight hours.
8. Abnormal Conditions, Bottom Hole Pressures and Potential Hazards- include anticipated bottomhole pressure and/or pressure gradient: No abnormal conditions are anticipated, formation is slightly over-pressured, estimated BHP: 800 PSI.
9. Any Other Aspects of this Proposal that should be Addressed:

#### B. THIRTEEN POINT SURFACE USE PLAN

The dirt contractor will be provided with an approved copy of the surface use plan of operations before initiating construction.

1. Existing Roads:
  - a. Proposed route to location (submit a map depicting access and well location).
  - b. Location of proposed well in relation to town or other reference point: 7.1 Miles southwest of Price, Utah.
  - c. Contact the Carbon County Road Department for use of county roads. The use of Carbon County roads will require an encroachment permit from the Carbon County Road Department.
  - d. Plans for improvement and/or maintenance of existing roads: Upgrade and maintain existing state or county roads.
  - e. Other:
2. Planned Access Roads:
  - a. Location (centerline): Sec. 29, T15S, R10E 940' FNL, 789' FWL
  - b. Length of new access to be constructed: 1300'
  - c. Length of existing roads to be upgraded: 0'
  - d. Maximum total disturbed width: 27'
  - e. Maximum travel surface width: 24'

- f. Maximum grades: 4%
- g. Turnouts: none
- h. Surface materials: In-place residual of Mancos Shale
- i. Drainage (crowning, ditching, culverts, etc): Roads will be crowned with water ditches on both sides. Water will be diverted around pad as necessary and 3 culverts will be placed along upgraded roadway.
- j. Cattleguards: none
- k. Length of new and/or existing roads which lie outside the lease boundary for which a BLM right-of-way is required: N/A
- l. Other:

Surface disturbance and vehicular travel will be limited to the approved location access road. Any additional area needed must be approved by the Area Manager in advance.

If a right-of-way is necessary, no surface disturbing activities shall take place on the subject right-of-way until the associated APD is approved. The holder will adhere to conditions of approval in the Surface Use Program of the approved APD, relevant to any right-of-way facilities.

If a right-of-way is secured, boundary adjustments in the lease or unit shall automatically amend this right-of-way to include that portion of the facility no longer contained within the lease or unit. In the event of an automatic amendment to this right-of-way grant, the prior on-lease/unit conditions of approval of this facility will not be affected even though they would now apply to facilities outside of the lease/unit as a result of a boundary adjustment. Rental fees, if appropriate shall be recalculated based on the conditions of this grant and the regulations in effect at the time of an automatic amendment.

If the well is productive, the access road will be rehabilitated or brought to Resource (Class III) Road Standards within 60 days of dismantling the rig. If upgraded, the access road must be maintained at these standards until the well is properly abandoned. If this time frame cannot be met, the Area Manager will be notified so that temporary drainage control can be installed along the access road.

- 3. Location of Existing Wells-on a map, show the location of all water, injection, disposal, producing and drilling wells within a one mile radius of the proposed well, and describe the status of each: See Attachment "B"
- 4. Location of Production Facilities:
  - a. On-site facilities: See Attachment "E"
  - b. Off-site facilities: none
  - c. The pipeline will come from an existing line along the old road to the west of the location. A 12" gas and 10" water line will be installed on the southwest side of the access road, power will be located on the northeast side.

All permanent (in place for six months or longer) structures constructed or installed (including oil well pump jacks) will be painted a flat, non-reflective color to match the standard environmental colors, as determined by the Rocky Mountain Five-State Interagency Committee. All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) may be excluded. Colors will be as follows: Olive Black

If a gas meter run is constructed, it will be located on lease within 500 feet of the wellhead. The gas flowline will be buried from the wellhead to the meter and will be buried downstream of the meter until it leaves the pad. Meter runs will be housed and/or fenced. The gas meter shall be calibrated prior to first sales and shall be calibrated quarterly thereafter. All gas production and measurement shall comply with the provisions of 43 CFR § 3162.7-3, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3.

If a tank battery is constructed on this lease, it will be surrounded by a dike of sufficient capacity to contain 1 ½ times the storage capacity of the largest tank. All loading lines and valves will be placed inside the berm surrounding the tank battery. All oil production and measurement shall conform to the provisions of 43 CFR § 3162.7-3 and Onshore Oil and Gas Order No. 4

Production facilities on location may include a lined or unlined produced water pit as specified in NTL-2B. If water is produced from the well, an NTL-2B application must be submitted.

5. Location and Type of Water Supply:

All water needed for drilling purposes will be obtained from (describe location and/or show on a map): PRWID

A temporary water use permit for this operation will be obtained from the Utah State Engineer in Price, Utah at (435) 637-1303.

Water obtained on private land, or land administered by another agency, will require approval from the owner or agency for use of the land.

6. Source of Construction Material:

Pad construction material will be obtained from (if the source is Federally owned, show location on a map): Private Owner

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

7. Methods of Handling Waste Disposal:

Describe the methods and locations proposed for safe containment and disposal of waste material, e.g. cuttings, produced water, garbage, sewage, chemicals, etc.

The reserve pit will be lined with (native material, bentonite, synthetic material): Pit will be lined with native material unless otherwise designated by BLM officers prior to construction.

The reserve pit will be located at the: Northeast side of the location, and the pit walls will be sloped at no greater than 2 to 1.



The reserve pit shall be located in cut material, with at least 50% of the pit volume being below original ground level. Three sides of the reserve pit will be fenced before drilling starts. The fourth side will be fenced as soon as drilling is completed, and shall remain until the pit is dry. As soon as the reserve pit has dried, all areas not needed for production will be rehabilitated.

Trash must be contained in a trash cage and hauled away to an approved disposal site as necessary but no later than at the completion of drilling operations.

8. Ancillary Facilities: Garbage containers and portable toilets.
9. Well Site Layout - depict the pit, rig, cut and fill, topsoil, etc. on a plat with a scale of at least 1" = 50'.

All well, whether drilling, producing, suspended, or abandoned, will be identified in accordance with 43 CFR 3162.6.

Access to the well pad will be from: Northwest of location.

The blooie line will be located in the: Northeast, at least 100 feet from the well head.

To minimize the amount of fugitive dust and spray escaping from the blooie pit, the following blooie line deflection method will be employed: Water injection.

10. Plans for Restoration of the Surface:

The top 6 inches of topsoil material will be removed from the location and stockpiled separately on: adjacent land.

Topsoil along the access road will be reserved in place adjacent to the road.

Immediately upon completion of drilling, all equipment that is not necessary for production shall be removed.

The reserve pit and that portion of the location not needed for production will be reclaimed.

Before any dirt work to restore the location takes place, the reserve pit must be completely dry.

Reclaimed roads will have the berms and cuts reduced and will be closed to vehicle use.

All disturbed areas will be recontoured to replicate the natural slope.

The stockpiled topsoil will be evenly distributed over the disturbed area.

Prior to reseeding, all disturbed areas, including the access roads, will be scarified and left with a rough surface.

Seed will be broadcast or drilled between Sept. and Nov., or at a time specified by the BLM. If broadcast, a harrow or some other implement will be dragged over the seeded area to assure seed coverage.

The following seed mixture will be used:

BLM recommended mixture: Desert Shrub

The abandonment marker will be one of the following, as specified by BLM:

- 1) At least four feet above ground level,
- 2) At restored ground level, or
- 3) Below ground level.

In any case the marker shall be inscribed with the following: operator name, lease number, well name and surveyed description (township, range, section and either quarter-quarter or footages).

Additional requirements:

11. Surface and Mineral Ownership: BLM surface/BLM subsurface

12. Other Information:

a. Archeological Concerns: none

The operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts.

If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized officer (AO). Within five (5) working days, the AO will inform the operator as to:

- Whether the materials appear eligible for the National Register of Historic Places;
- The mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and
- A time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that the required mitigation has been completed, the operator will then be allowed to resume construction.

b. Threatened and Endangered Species Concerns: No

c. Wildlife Seasonal Restrictions (yes/no): See EIS

d. Off Location Geophysical Testing: N/A

e. Drainage crossings that require additional State or Federal approval: N/A

f. Other: N/A

13. Lessee's or Operator's Representative and Certification

Representative:

Name: Jean Semborski


Title: Permitting Specialist

Address: 6825 S. 5300 W. P.O. Box 851  
Price, Utah 84501

Phone No: (435) 613-9777 Fax (435) 613-9782

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exists; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by RGC and its contractors and subcontractors in conformity with this APD package and the terms and conditions under which it is approved. I also certify responsibility for the operations conducted on that portion of the leased lands associated with this application, with bond coverage being provided under BLM bond no. S304604. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.



Signature

Permitting Specialist

Title

12/7/2000

Date

### C. REQUIRED APPROVALS, REPORTS AND NOTIFICATIONS

Required verbal notifications are summarized in Table 1, attached.

Building Location- Contact the Resource Area, Natural Resource Protection Specialist at least 24 hours prior to commencing construction of location.

Spud- The spud date will be reported to the Resource Area Office 24 hours prior to spudding. Written notification in the form of a Sundry Notice (Form 3160-5) will be submitted the District Office within 24 hours after spudding, regardless of whether spud was made with a dry hole digger or big rig.

Daily Drilling Reports- Daily drilling reports shall detail the progress and status of the well and shall be submitted to the District Office on a weekly basis.

Monthly Reports of Operations- In accordance with Onshore Oil and Gas Order No. 1, this well shall be reported on Minerals Management Service (MMS) Form 3160, "Monthly Report of Operations," starting the month in which operations commence and continuing each month until the well is physically plugged and abandoned. This report will be filed directly with MMS.

Sundry Notices- There will be no deviation from the proposed drilling and/or workover program without prior approval from the Assistant District Manager. "Sundry Notices and Reports on Wells: (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2. Safe drilling and operating practices must be observed.

Drilling Suspensions- Operations authorized by this permit shall not be suspended for more than 30 days without prior approval of the Authorized Officer. All conditions of this approval shall be applicable during any operations conducted with a replacement rig.

Undesirable Events- Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be immediately reported to the Resource Area in accordance with requirements of NTL-3A.

Cultural Resources- If cultural resources are discovered during construction, work that might disturb the resources is to stop, and the Area Manager is to be notified.

First Production- Should the well be successfully completed for production, the Assistant District Manager, Minerals Division will be notified when the well is placed in producing status. Such notification may be made by phone, but must be followed by a sundry notice or letter not later than five (5) business days following the date on which the well is placed into production.

A first production conference will be scheduled as soon as the productivity of the well is apparent. This conference should be coordinated through the Resource Area Office. The Resource Area Office shall be notified prior to the first sale.

Well Completion Report- Whether the well is completed as a dry hole or as a producer, “Well Completion and Recompletion Report and Log” (Form 3160-4) will be submitted to the District Office not later than thirty (30) days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs, core descriptions, core analysis, well test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings and/or samples) will be submitted when requested by the Assistant District Manager.

Venting/Flaring of Gas-NTL-4A allows venting/flaring of gas during the initial well evaluation period not to exceed 30 days or 50 MMcf. Venting/flaring beyond the initial test period threshold must be approved by the District Office.

Off-Lease Measurement, Storage, Commingling- Prior approval must be obtained from the Assistant District Manager for off-lease measurement, off-lease storage and/or commingling (either down-hole or at the surface).

Plugging and Abandonment- If the well is completed as a dry hole, plugging instructions must be obtained from the BLM, Moab District Office prior to initiating plugging operations. Table 1 of this document provides the after-hours phone numbers of personnel who are authorized to give plugging instructions.

A “Subsequent Report of Abandonment” (Form 3160-5) will be filed with the Assistant District Manager, Minerals Divisions within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Upon completion of approved plugging, a regulation marker will be erected in accordance with 43 CFR 3162.6. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the Area Manager or his representative, or the appropriate surface managing agency.

TABLE 1  
NOTIFICATIONS

Notify Don Stephens of the Price Resource Area, at (435)636-3608 for the following:

2 days prior to commencement of dirt work, construction or reclamation;

1 day prior to spudding;

50 feet prior to reaching surface and intermediate casing depths;


3 hours prior to testing BOPE;

12 hours prior to reaching kickoff point depth (if applicable).

If the person at the above number cannot be reached, notify the Moab District Office at (435) 259-6111. If unsuccessful, notify one of the people listed below.

Well abandonment operations require 24 hour advance notice and prior approval. In the case of newly drilled dry holes, verbal approval can be obtained by calling the Moab District Office, Branch of Fluid Minerals at (435) 259-6111. If approval is needed after work hours, you may contact the following:

|                                |                        |
|--------------------------------|------------------------|
| Eric Jones, Petroleum Engineer | Office: (435) 259-6111 |
|                                | Home: (435) 259-2214   |






Elevation Ungraded Ground at Location Stake = 5718.0'  
 Elevation Graded Ground at Location Stake = 5717.5'



|                               |  |
|-------------------------------|--|
| DRAWN BY:<br><b>P. BOYLEN</b> | <br><b>Castle Valley</b><br>3266 South 126 West<br>Price, Utah 84501<br>(801) 637-9300<br>FAX (801) 637-2833 |
| CHECKED BY:<br><b>J.S.H.</b>  |  |
| DATE:<br><b>11/29/00</b>      |  |
| SCALE:<br><b>1"=50'</b>       |  |
| JOB NO.<br><b>644</b>         |  |
| DRAWING NO.<br><b>A-2</b>     | <b>Services</b>  |
| SHEET <b>2</b> OF <b>4</b>    | <b>River Gas Corporation</b><br>Location Layout<br>Section 29, T15S, R10E, S.L.B.&M.<br>Well # 29-455        |


1"=10'  
X-Section  
Scale  
1"=40'

Slope = 1 1/2 : 1  
(Except Pit)  
Pit Slope = 1 : 1




### APPROXIMATE YARDAGES

|                        |                          |
|------------------------|--------------------------|
| CUT                    |                          |
| (6") Topsoil Stripping | = 750.0 Cu. Yds.         |
| Remaining Location     | = 1,667 Cu. Yds.         |
| <b>TOTAL CUT</b>       | <b>= 2,417 Cu. Yds.</b>  |
| <b>TOTAL FILL</b>      | <b>= 877.41 Cu. Yds.</b> |

|                               |  |
|-------------------------------|--|
| DRAWN BY:<br><b>P. BOYLEN</b> |   |
| CHECKED BY:<br><b>J.S.H.</b>  |  |
| DATE:<br><b>11/29/00</b>      |  |
| SCALE:<br><b>As Shown</b>     |  |
| JOB NO.<br><b>644</b>         |  |
| DRAWING NO.<br><b>C-1</b>     | 3266 South 125 West<br>Price, Utah 84501<br>(801) 637-9300<br>FAX (801) 637-2833   |
| SHEET <b>3</b> OF <b>4</b>    | <b>Servicos</b><br><b>River Gas Corporation</b><br><b>Typical Cross Sections</b><br><b>Section 29, T15S, R10E, S.L.B.&amp;M.</b><br><b>Well # 29-455</b> |



DRAWN BY:  
**P. BOYLEN**CHECKED BY:  
**J.S.H.**DATE:  
**11/30/00**SCALE:  
**1"=2000'**JOB NO.  
**644**

DRAWING NO.


**L-1**

SHEET 4 OF 4

**Castle Valley**140 North Cedar Hills Dr.  
Price, Utah 84501  
(801) 637-3557  
FAX (801) 637-3593

Sevens

**River Gas Corporation**  
 Section 29, T15S, R10E, S.L.B.&M.  
 Carbon County, Utah  
 Well# 29-455



# USA 29-455

## Section 29, T15S, R10E

Universal Transverse Mercator  
12 North  
NAD 1927 (Conus)




Scale 1:75000  
0 8000  
Feet

usa29455.ssf  
12/07/2000  
Pathfinder Office  
 **Trimble**

# APPROXIMATE LAYOUT OF RIG & EQUIPMENT



LIGHT  
PLANT



LIGHT  
PLANT

40'

PIPE TRAILER

O HOLE

8'

SURFACE  
CUTTINGS  
PIT

20'

MAIN  
PIT

FUEL TANK

DOG HOUSE

40'

BOOSTER

COMPRESSOR


45'

RIG

AUX  
COMP.

FRAC TANK


ANCHOR (TYP. 4 PL.)




RIVER GAS CORP.  
WELL SITE LAYOUT  
215' X 175'

Exhibit "E"

# TYPICAL ROAD CROSS-SECTION




# DIVERTER HEAD



- (1) 2" 5M FLANGED CHOKE
- (2) 2" 5M GATE VALVE (FLANGED)
- (3) 2" 5M STUDDED CROSS
- (4) 2" 5M GATE VALVE (FLANGED)
- (5) 2" 5M FLANGED CHOKE
- (6) 2" 5M GATE VALVE (FLANGED)
- (7) 2" LINE
- (8) 2" 5M GATE VALVE (FLANGED)
- (9) 3000# GAUGE

NOTE:  
NUMBER 8 GATE VALVE  
SITS ON TOP OF MANIFOLD  
BETWEEN STUDDED CROSS  
AND 3000# GAUGE.



AND A NEW 2" BALL VALVE  
FULL OPEN 5000PSI

MANIFOLD

**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 12/11/2000

API NO. ASSIGNED: 43-007-30507

WELL NAME: USA 29-455

OPERATOR: RIVER GAS CORPORATION ( N1605 )

CONTACT: JEAN SEMBORSKI

PHONE NUMBER: 435-613-9777

**PROPOSED LOCATION:**

NWNW 29 150S 100E

SURFACE: 0940 FNL 0789 FWL

BOTTOM: 0940 FNL 0789 FWL

CARBON

UNDESIGNATED ( 2 )

LEASE TYPE: 1-Federal

LEASE NUMBER: UTU-73075

SURFACE OWNER: 1-Federal

PROPOSED FORMATION: FRSD

INSPECT LOCATN BY: / /

| Tech Review | Initials | Date |
|-------------|----------|------|
| Engineering |          |      |
| Geology     |          |      |
| Surface     |          |      |

**RECEIVED AND/OR REVIEWED:**

☒ Plat

☒ Bond: Fed[1] Ind[] Sta[] Fee[]  
(No. S304604 )

☐ Potash (Y/N)

☐ Oil Shale (Y/N) \*190-5 (B) or 190-3

☒ Water Permit  
(No. PRWID )

☐ RDCC Review (Y/N)  
(Date: \_\_\_\_\_ )

☐ Fee Surf Agreement (Y/N)

**LOCATION AND SITING:**

       R649-2-3. Unit \_\_\_\_\_

       R649-3-2. General

       Siting: 460 From Qtr/Qtr & 920' Between Wells

       R649-3-3. Exception

☒ Drilling Unit

Board Cause No: 137-2(B)

Eff Date: 2-25-82

Siting: 1000' fr. Dr. Unit Boundary

       R649-3-11. Directional Drill


**COMMENTS:**

Need add'l info. "Ev. Loc / 137-2(B)" (Rec'd 12-11-2000)

**STIPULATIONS:**

① FEDERAL APPROVAL






Utah Oil Gas and Mining

OPERATOR: RIVER GAS CORP (N1605)

FIELD: UNDESIGNATED (002)

SEC. 29, T15S, R10E,

COUNTY: CARBON CAUSE: 137-2(B) (160')





State of Utah  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt  
Governor

Kathleen Clarke  
Executive Director

Lowell P. Braxton  
Division Director

1594 West North Temple, Suite 1210  
PO Box 145801  
Salt Lake City, Utah 84114-5801  
801-538-5340  
801-359-3940 (Fax)  
801-538-7223 (TDD)

January 8, 2001

River Gas Corporation  
PO Box 851  
Price, UT 84501

Re: USA 29-455 Well, 940' FNL, 789' FWL, NW NW, Sec. 29, T. 15 South, R. 10 East,  
Carbon County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-007-30507.

Sincerely,

A handwritten signature in black ink, appearing to read 'John R. Baza'.

John R. Baza  
Associate Director

er

Enclosures

cc: Carbon County Assessor  
Bureau of Land Management, Moab District Office

**Operator:** River Gas Corporation  
**Well Name & Number** USA 29-455  
**API Number:** 43-007-30507  
**Lease:** UTU-73075

**Location:** NW NW      **Sec.** 29      **T.** 15 South      **R.** 10 East

### **Conditions of Approval**

**1. General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

**2. Notification Requirements**

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

**3. Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

**4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.**

LAW OFFICES  
**PRUITT, GUSHEE & BACHTELL**

SUITE 1850 BENEFICIAL LIFE TOWER  
SALT LAKE CITY, UTAH 84111-1495

(801) 531-8446

TELECOPIER (801) 531-8468

E-MAIL: mail@pgblaw.com

THOMAS W. BACHTELL  
A. JOHN DAVIS, III  
JOHN W. ANDERSON  
FREDERICK M. MACDONALD  
GEORGE S. YOUNG  
ANGELA L. FRANKLIN  
JOHN S. FLITTON  
MICHAEL S. JOHNSON  
WILLIAM E. WARD

SENIOR COUNSEL:  
ROBERT G. PRUITT, JR.  
OLIVER W. GUSHEE, JR.

OF COUNSEL:  
ROBERT G. PRUITT, III  
BRENT A. BOHMAN

January 29, 2001

**HAND DELIVERED**

Mr. Jim Thompson  
Utah Division of Oil, Gas & Mining  
1594 W. North Temple  
Salt Lake City, UT 84116

*Re: River Gas/Phillips Merger*

Dear Mr. Thompson:

As you may know, River Gas Corporation ("RGC") merged into Phillips Petroleum Company ("Phillips") effective December 31, 2000 at 11:59 p.m. I have enclosed a Certificate of Articles of Merger issued by the Utah Department of Commerce and, although duplicative, a sundry notice formally evidencing the merger for your records, and a list of all wells, including injection wells, formerly operated by RGC.

Please change the Division's records to reflect the change in operator of these wells from RGC to Phillips. All operational questions should be directed to Phillips at the following address:


Phillips Petroleum Company  
Attn: Billy Stacy, Operations Manager  
P.O. Box 3368  
Englewood, CO 80155-3368  
Telephone No.: (720) 344-4984

Phillips currently has a bond on file with the Division (a copy of which is enclosed for your reference), but I understand an \$80,000 Letter of Credit is in the process of being substituted.

Mr. Jim Thompson  
January 29, 2001  
Page 2

On behalf of Phillips, I thank you for your cooperation. Should you have any further questions or concerns, please do not hesitate to contact me.

Yours very truly,

A handwritten signature in black ink, appearing to read "Frederick M. MacDonald", with a long, sweeping horizontal stroke extending to the left.

Frederick M. MacDonald

FMM:cs  
2078.16  
Enclosures  
cc: W. H. Rainbolt  
Billy Stacy



Utah Department of Commerce  
Division of Corporations & Commercial Code  
160 East 300 South, 2nd Floor, Box 146705  
Salt Lake City, UT 84114-6705  
Phone: (801) 530-4849  
Toll Free: (877) 526-3994 Utah Residents  
Fax: (801) 530-6438  
Web site: <http://www.commerce.state.ut.us>

Registration Number: 562960-0143  
Business Name: PHILLIPS PETROLEUM COMPANY  
Registered Date: JUNE 14, 1946


01/12/01

---

## CERTIFICATE OF ARTICLES OF MERGER

THE UTAH DIVISION OF CORPORATIONS AND COMMERCIAL CODE ("DIVISION") HEREBY CERTIFIES THAT

ARTICLES OF MERGER WERE FILED WITH THIS OFFICE ON DECEMBER 12, 2000 MERGING RIVER GAS CORPORATION, A CORPORATION OF THE STATE OF ALABAMA, INTO PHILLIPS PETROLEUM COMPANY, THE SURVIVING CORPORATION WHICH IS OF THE STATE OF DELAWARE, AS APPEARS OF RECORD IN THE OFFICE OF THE DIVISION.



*Ric Campbell*

Ric Campbell  
Acting Division Director of  
Corporations and Commercial Code

---

Dept. of Professional Licensing  
(801)530-6628

Real Estate  
(801)530-6747

Public Utilities  
(801)530-6651

Securities  
(801)530-6600

Consumer Protection  
(801)530-6601

68N JOURNAL  
00171191

State of Delaware  
Office of the Secretary of State

PAGE 1

ts

12/13/2000  
Receipt Number: 188532  
Amount Paid: \$145.00

I, EDWARD J. FREEL, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF OWNERSHIP, WHICH MERGES:

"RIVER GAS CORPORATION", A ALABAMA CORPORATION,  
WITH AND INTO "PHILLIPS PETROLEUM COMPANY" UNDER THE NAME OF "PHILLIPS PETROLEUM COMPANY", A CORPORATION ORGANIZED AND EXISTING UNDER THE LAWS OF THE STATE OF DELAWARE, AS RECEIVED AND FILED IN THIS OFFICE THE SIXTH DAY OF DECEMBER, A.D. 2000, AT 10 O'CLOCK A.M.

AND I DO HEREBY FURTHER CERTIFY THAT THE EFFECTIVE DATE OF THE AFORESAID CERTIFICATE OF OWNERSHIP IS THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2000, AT 11:59 O'CLOCK A.M.

A FILED COPY OF THIS CERTIFICATE HAS BEEN FORWARDED TO THE NEW CASTLE COUNTY RECORDER OF DEEDS.

12-12-00P04:02 RCVD

TAF  
FILED  
DEC 12 2000

Utah Div. Of Corp. & Comm. Code

State of Utah  
Department of Commerce  
Division of Corporations and Commercial Code  
I Hereby certify that the foregoing has been filed and approved on this 12 day of Dec 20 2000 in the office of this Division and hereby issue this Certificate thereof.

Examiner

12/13/2000



RIC CAMPBELL  
ACTING DIRECTOR



Edward J. Freel

Edward J. Freel, Secretary of State

AUTHENTICATION: 0837738

0064324 8100M

001609453

DATE: 12-07-00

## CERTIFICATE OF OWNERSHIP AND MERGER

OF

RIVER GAS CORPORATION

(an Alabama corporation)

into

Phillips Petroleum Company

(a Delaware corporation)

It is hereby certified that:

1. Phillips Petroleum Company [hereinafter sometimes referred to as the "Corporation"] is a business corporation of the State of Delaware.

2. The Corporation is the owner of all of the outstanding shares of each class of stock of River Gas Corporation, which is a business corporation of the State of Alabama.

3. The laws of the jurisdiction of organization of River Gas Corporation permit the merger of a business corporation of that jurisdiction with a business corporation of another jurisdiction.

4. The Corporation hereby merges River Gas Corporation into the Corporation.

5. The following is a copy of the resolutions adopted on November 21, 2000 by the Board of Directors of the Corporation to merge the said River Gas Corporation into the Corporation:

"1. Phillips Petroleum Company, which is a business corporation of the State of Delaware and is the owner of all of the outstanding shares of River Gas Corporation, which is a business corporation of the State of Alabama, hereby merges River Gas Corporation into Phillips Petroleum Company pursuant to the provisions of the Alabama Business Corporation Act and pursuant to the

12-12-00P04:02 RCVD



provisions of Section 253 of the General Corporation Law of Delaware.

"2. The separate existence of River Gas Corporation shall cease at the effective time and date of the merger pursuant to the provisions of the Alabama Business Corporation Act; and Phillips Petroleum Company shall continue its existence as the surviving corporation pursuant to the provisions of Section 253 of the General Corporation Law of Delaware.

"3. The Articles of Incorporation of Phillips Petroleum Company are not amended in any respect by this Plan of Merger.

"4. The issued shares of River Gas Corporation shall not be converted or exchanged in any manner, but each said share which is issued immediately prior to the effective time and date of the merger shall be surrendered and extinguished.

"5. Each share of Phillips Petroleum Company outstanding immediately prior to the effective time and date of the merger is to be an identical outstanding share of Phillips Petroleum Company at the effective time and date of the merger.

"6. No shares of Phillips Petroleum Company and no shares, securities, or obligations convertible into such shares are to be issued or delivered under this Plan of Merger.

"7. The Board of Directors and the proper officers of Phillips Petroleum Company are hereby authorized, empowered, and directed to do any and all acts and things, and to make, execute, deliver, file, and/or record any and all instruments, papers, and documents which shall be or become necessary, proper, or convenient to carry out or put into effect any of the provisions of this Plan of Merger or of the merger herein provided for."

" This Company approves that the effective time and date of the merger herein provided for in the State of Alabama shall be 11:59 p.m. on December 31, 2000."

"Any Vice President, the Treasurer, any Assistant Treasurer, the Secretary, any Assistant Secretary, and each of them severally, be and hereby is authorized to make, execute,

deliver, file, and/or record any and all instruments, papers, and documents which shall be or become necessary, proper, or convenient to carry out or put into effect any of the provisions of these resolutions and to do or cause to be done all such acts as are necessary to give effect to the purpose and intent of the approval herein set forth."

6. This Certificate of Ownership and Merger shall be effective at 11:59 p.m. on December 31, 2000.

Executed on November 27, 2000

Phillips Petroleum Company

  
\_\_\_\_\_  
N. A. Loftis, Assistant Secretary

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☐ GAS ☒ OTHER:

2. Name of Operator:

River Gas Corporation

3. Address and  
Telephone Number:

6825 S. 5300 W. P.O. Box 851 Price, Utah 84501 (435) 613-9777

4. Location of Well  
Footages:

QQ, Sec., T., R., M.:

SLB & M

5. Lease Designation and Serial Number:

6. If Indian, Allottee or Tribe Name:

7. Unit Agreement Name:

8. Well Name and Number:

9. API Well Number:

10. Field or Pool, or Wildcat:

County: Carbon County

State: Utah

### 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

#### NOTICE OF INTENT (Submit in Duplicate)

- |   |   |
|---|---|
| <input type="checkbox"/> Abandon                                    | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Repair Casing                              | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans                            | <input type="checkbox"/> Recomplete           |
| <input type="checkbox"/> Convert to Injection                       | <input type="checkbox"/> Reperforate          |
| <input type="checkbox"/> Fracture Treat or Acidize                  | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Multiple Completion                        | <input type="checkbox"/> Water Shut-Off       |
| <input checked="" type="checkbox"/> Other <u>Change of Operator</u> |   |
| Approximate date work will start _____                              |   |

#### SUBSEQUENT REPORT (Submit Original Form Only)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandon *                 | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Repair Casing             | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans           | <input type="checkbox"/> Reperforate          |
| <input type="checkbox"/> Convert to Injection      | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off       |
| <input type="checkbox"/> Other _____               |   |
| Date of work completion _____                      |   |

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

\* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please be advised that River Gas Corporation is transferring ownership of the attached list of wells to Phillips Petroleum Company 9780 Mt. Pyramid Court, Englewood, CO 80112.

Please direct all correspondence and reports to: Phillips Petroleum Company P.O. Box 3368, Englewood, CO 80155-3368.

Effective 1/1/01.

13.

Name & Signature: Cal Hurtt



Title: Development Manager

Date: 12/19/00

(This space for state use only)



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, UT 84145-0155

In Reply Refer To:  
3106  
UTU-47157 et al  
(UT-932)

JAN 30 2001

### NOTICE

Phillips Petroleum Company : Oil and Gas  
Attn: W. H. Rainbolt, Rocky Mtn. Region-Land :  
Box 1967 :  
Houston, TX 77251-1967 :

### Merger Recognized

Acceptable evidence has been filed in this office concerning the merger of River Gas Corporation into Phillips Petroleum Company with Phillips Petroleum Company being the surviving entity.

The oil and gas lease files and rights-of-way files identified on the enclosed exhibit have been noted as to the merger. The exhibit is the list supplied by the representative of the companies, and verified by our computerized records. We have not adjudicated the case files to determine if the entity affected by the merger holds an interest in the leases identified, nor have we attempted to identify leases where the entity is the operator on the ground, maintaining no vested record title or operating rights interest. We are notifying the Minerals Management Service and all applicable BLM offices of the merger by a copy of this notice. If additional documentation for a change of operator is required by our Field Offices, you will be contacted by them.

By recognition of the merger the obligor is automatically changed by operation of law from River Gas Corporation to Phillips Petroleum Company on Letter of Credit No. P-207337 (BLM Bond No. UT0829). A rider to BLM Bond No. ES0048 assuming any and all liabilities of BLM Bond No. UT0829 must be submitted for approval to the Eastern States Office, Attn: Bill Forbes, 7450 Boston Boulevard, Springfield, VA 22153. After the rider is approved, the Letter of Credit will be returned to the financial institution that issued it.

**ROBERT LOPEZ**

Robert Lopez  
Chief, Branch of  
Minerals Adjudication

Enclosure  
Exhibit of Leases

RECEIVED

JAN 30 2001

DIVISION OF  
OIL, GAS AND MINING

cc: Moab Field Office  
Vernal Field Office  
Price Field Office  
MMS-Reference Data Branch, MS 3130, P.O. Box 5860, Denver, CO 80217  
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC, UT 84114  
The Chase Manhattan Bank, Attn: Standby Letter of Credit Dept., 4 Chase Metrotech Center, 8<sup>th</sup> Floor  
Brooklyn, NY 11245  
Teresa Thompson (UT-931)  
LaVerne Steah (UT-942)  
Pruitt, Gushee & Bachtell, Attn: Frederick M. MacDonald, Suite 1850 Beneficial Life Tower,  
Salt Lake City, Utah 84111-1495  
BLM, Eastern States Office (Attn: Bill Forbes)

## **RGC/Phillips Merger**

### **List of Affected BLM Leases and Rights-of-Way**

#### **A. Oil & Gas Leases**

|           |           |           |
|-----------|-----------|-----------|
| UTU-47157 | UTU-70219 | UTU-75016 |
| UTU-49631 | UTU-70400 | UTU-75019 |
| UTU-50645 | UTU-71390 | UTU-75021 |
| UTU-51584 | UTU-72003 | UTU-75022 |
| UTU-53872 | UTU-72004 | UTU-76332 |
| UTU-57821 | UTU-72350 | UTU-76334 |
| UTU-60402 | UTU-72355 | UTU-77351 |
| UTU-60925 | UTU-72358 | UTU-77353 |
| UTU-61154 | UTU-72377 | UTU-77354 |
| UTU-61155 | UTU-72470 | UTU-78408 |
| UTU-61158 | UTU-72477 | UTU-78409 |
| UTU-61547 | UTU-72624 | UTU-78410 |
| UTU-61548 | UTU-72723 | UTU-78411 |
| UTU-62145 | UTU-72724 | UTU-78412 |
| UTU-62276 | UTU-72746 | UTU-78413 |
| UTU-65298 | UTU-73004 | UTU-78782 |
| UTU-65300 | UTU-73075 | UTU-78783 |
| UTU-65302 | UTU-73330 | UTU-79150 |
| UTU-65303 | UTU-73331 | UTU-79151 |
| UTU-67621 | UTU-73523 | UTU-79152 |
| UTU-67839 | UTU-73752 | UTU-79153 |
| UTU-67906 | UTU-73884 | UTU-79154 |
| UTU-68314 | UTU-74376 | UTU-79155 |
| UTU-69449 | UTU-75015 | UTU-79159 |

#### **B. Rights-of-Way**

|           |              |              |
|-----------|--------------|--------------|
| UTU-73226 | UTU-77141    | UTU-77976    |
| UTU-74319 | UTU-77141-01 | UTU-77989    |
| UTU-74320 | UTU-77151    | UTU-77989-01 |
| UTU-76610 | UTU-77151-01 |              |
| UTU-76629 | UTU-77154    |              |

**OPERATOR CHANGE WORKSHEET****ROUTING**

|        |                                     |                  |                                     |
|--------|-------------------------------------|------------------|-------------------------------------|
| 1. GLH |                                     | 4-KAS            | <input checked="" type="checkbox"/> |
| 2. CDW | <input checked="" type="checkbox"/> | 5- <del>PP</del> | <input checked="" type="checkbox"/> |
| 3. JLT |                                     | 6-FILE           |                                     |

Enter date after each listed item is completed

Change of Operator (Well Sold)

Designation of Agent

Operator Name Change (Only)

**X Merger**The operator of the well(s) listed below has changed, effective: **12-31-2000**

|  |
|--|
| <b>FROM:</b> (Old Operator):           |
| RIVER GAS CORPORATION                  |
| Address: 6825 S. 5300 W. P. O. BOX 851 |
|  |
| PRICE, UT 84501                        |
| Phone: 1-(435)-613-9777                |
| Account N1605                          |
|  |

|                             |
|-----------------------------|
| <b>TO:</b> ( New Operator): |
| PHILLIPS PETROLEUM COMPANY  |
| Address: P. O. BOX 3368     |
|                             |
| ENGLEWOOD, CO 80155-3368    |
| Phone: 1-(720)-344-4984     |
| Account N1475               |
|                             |

**CA No.****Unit: DRUNKARDS WASH****WELL(S)**

| NAME       | API NO.      | ENTITY NO. | SEC. TWN RNG | LEASE TYPE | WELL TYPE | WELL STATUS |
|------------|--------------|------------|--------------|------------|-----------|-------------|
| USA 15-420 | 43-007-30690 | 99999      | 15-15S-08E   | FEDERAL    | GW        | APD         |
| USA 15-422 | 43-007-30691 | 99999      | 15-15S-08E   | FEDERAL    | GW        | APD         |
| USA 22-466 | 43-007-30700 | 99999      | 22-15S-08E   | FEDERAL    | GW        | APD         |
| USA 23-467 | 43-007-30503 | 99999      | 23-15S-08E   | FEDERAL    | GW        | APD         |
| USA 23-445 | 43-007-30650 | 99999      | 23-15S-08E   | FEDERAL    | GW        | APD         |
| USA 23-451 | 43-007-30704 | 99999      | 23-15S-08E   | FEDERAL    | GW        | APD         |
| USA 24-449 | 43-007-30705 | 99999      | 24-15S-08E   | FEDERAL    | GW        | APD         |
| USA 25-459 | 43-007-30505 | 99999      | 25-15S-08E   | FEDERAL    | GW        | APD         |
| USA 29-455 | 43-007-30507 | 99999      | 29-15S-10E   | FEDERAL    | GW        | APD         |
| USA 31-309 | 43-007-30515 | 99999      | 31-15S-10E   | FEDERAL    | GW        | APD         |
| USA 1-425  | 43-015-30418 | 99999      | 01-16S-09E   | FEDERAL    | GW        | APD         |
| USA 10-363 | 43-015-30419 | 99999      | 10-16S-09E   | FEDERAL    | GW        | APD         |
| USA 10-364 | 43-015-30425 | 99999      | 10-16S-09E   | FEDERAL    | GW        | APD         |
| USA 11-313 | 43-015-30351 | 99999      | 11-16S-09E   | FEDERAL    | GW        | APD         |
| USA 11-315 | 43-015-30354 | 99999      | 11-16S-09E   | FEDERAL    | GW        | APD         |
| USA 11-316 | 43-015-30355 | 99999      | 11-16S-09E   | FEDERAL    | GW        | APD         |
| USA 12-385 | 43-015-30398 | 99999      | 12-16S-09E   | FEDERAL    | GW        | APD         |
| USA 12-426 | 43-015-30409 | 99999      | 12-16S-09E   | FEDERAL    | GW        | APD         |
| USA 21-429 | 43-015-30415 | 99999      | 21-16S-09E   | FEDERAL    | GW        | APD         |
| USA 21-428 | 43-015-30416 | 99999      | 21-16S-09E   | FEDERAL    | GW        | APD         |

**OPERATOR CHANGES DOCUMENTATION**

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 01/29/2001
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 01/29/2001
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 02/15/2001

4. Is the new operator registered in the State of Utah: YES Business Number: 562960-0143
5. If **NO**, the operator was contacted contacted on: \_\_\_\_\_
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the (merger, name change, or operator change for all wells listed on Federal or Indian leases on: 01/30/2001
7. **Federal and Indian Units:** The BLM or BIA has approved the successor of unit operator for wells listed on: N/A
8. **Federal and Indian Communization Agreements ("CA"):** The BLM or the BIA has approved the operator change for all wells listed involved in a CA on: N/A
9. **Underground Injection Control ("UIC") Pro:** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

---

**DATA ENTRY:**

1. Changes entered in the **Oil and Gas Database** on: 02/15/2001
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 02/15/2001
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

---

**STATE BOND VERIFICATION:**

1. State well(s) covered by Bond No.: N/A

---

**FEE WELLS - BOND VERIFICATION/LEASE INTEREST OWNER NOTIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed has furnished a bond: N/A
2. The **FORMER** operator has requested a release of liability from their bond on: N/A  
The Division sent response by letter on: N/A
3. (R649-2-10) The **FORMER** operator of the Fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

---

**FILMING:**

1. All attachments to this form have been **MICROFILMED** on: 2-21-01

---

**FILING:**

1. **ORIGINALS/COPIES** of all attachments pertaining to each individual well have been filled in each well file on: \_\_\_\_\_

---

**COMMENTS:**

---

---

---

---

---

---

---



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

|   |  |  |
|---|--|--|
| 1a. TYPE OF WORK<br><b>DRILL</b> <input checked="" type="checkbox"/> <b>DEEPEN</b> <input type="checkbox"/>   |  | 5. LEASE DESIGNATION AND SERIAL NO.<br>UTU-73075   |
| b. TYPE OF WELL<br>OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/> SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/> |  | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME<br>N/A  |
| 2. NAME OF OPERATOR<br><del>REVER GAS CORPORATION</del> <i>Phillips Petroleum Company</i>   |  | 7. UNIT AGREEMENT NAME<br>Drunkards Wash UTU-67921X  |
| 3. ADDRESS AND TELEPHONE NO.<br>6825 S. 5300 W. P.O. Box 851 Price, Utah 84501 (435) 613-9777   |  | 8. FARM OR LEASE NAME, WELL NO.<br>USA 29-455  |
| 4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. *)<br>At surface 940' FNL, 789' FWL<br>At proposed prod. zone   |  | 9. API WELL NO.<br>43-007-30507  |
| 14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*<br>7.1 miles southwest of Price, Utah.  |  | 10. FIELD AND POOL, OR WILDCAT<br>Drunkards Wash   |
| 15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drig. unit line, if any)<br>539'   | 16. NO. OF ACRES IN LEASE<br>2232.19 Acres | 11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA<br>NW/4, NW/4, Sec. 29, T15S, R10E, SLB&M |
| 18. DISTANCE FROM PROPOSED LOCATION TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.<br>2250'   | 19. PROPOSED DEPTH<br>1750'                | 12. COUNTY OR PARISH<br>Carbon   |
| 21. ELEVATIONS (Show whether DF, RT, GR, etc.)<br>5718' GR  |  | 13. STATE  |
| 20. ROTARY OR CABLE TOOLS<br>Rotary   |  | 17. NO. OF ACRES ASSIGNED TO THIS WELL<br>160 acres  |
| 22. APPROX. DATE WORK WILL START*<br>April 2001   |  |  |

| 23. PROPOSED CASING AND CEMENTING PROGRAM |                       |                 |               |  |
|---|-----------------------|-----------------|---------------|--|
| SIZE OF HOLE                              | GRADE, SIZE OF CASING | WEIGHT PER FOOT | SETTING DEPTH | QUANTITY OF CEMENT   |
| 14"                                       | 12-3/4"               | Conductor       | 40'           |  |
| 11"                                       | J-55 8-5/8"           | 24 #/ft         | 175'          | 68 sks G+2% CaCl + 1/4# per sack floccel                             |
| 7-7/8"                                    | N-80 5-1/2"           | 17 #/ft         | 1740'         | 117 sks 50/50 POZ + 8%gel+2%CaCl+10%extender. 97 sks "G" thixotropic |

RECEIVED

MAR 30 2001

DIVISION OF  
OIL, GAS AND MINING

ORIGINAL

CONFIDENTIAL

FLARING OR VENTING OF  
GAS IS SUBJECT TO NTL 4-A  
Dated 1/1/80

CONDITIONS OF APPROVAL ATTACHED

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED *Jean Seabright* TITLE Permitting Specialist DATE 12/7/00  
(This space for Federal or State office use)

PERMIT NO. \_\_\_\_\_ APPROVAL DATE \_\_\_\_\_


Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY \_\_\_\_\_ TITLE Assistant Field Manager, DATE MAR 27 2001  
Division of Resources

\*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency or the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

# Range 10 East



## Location

The Bearings Indicated are per the recorded plat obtained from the U.S. Land Office. The well location was determined using a Trimble 4400 GPS Unit. UTM Coordinates listed are NAD27 based, Zone 12 North and in Meters.

## Basis Of Elevation:


Basis of Elevation of 5612' as indicated in the NE Corner of Section 20, Township 15 South, Range 10 East, Salt Lake Base and Meridian, as shown on the Poison Spring Bench Quadrangle 7.5 Minute Series Map.

## Description of Well Point

Proposed Drill Hole located in the NW 1/4 NW 1/4 of Section 29; being 939.71' South and 788.96' East from the NW Corner of Section 29, T15S, R10E, Salt Lake Base & Meridian.

## Surveyor's Certificate:

I, John S. Huefner, a Registered Licensed Land Surveyor, holding Certificate #144842, State of Utah, do hereby certify that the information on this drawing is a true and accurate survey of the land, and was conducted under my personal supervision, as shown hereon.




## LEGEND:

- Drill Hole Location
- ⊕ Found Section Corner Monumented w/ Brass Cap unless indicated otherwise.
- Section Corner searched for but not found



SCALE:



|                               |  |   |
|-------------------------------|--|---|
| DRAWN BY:<br><b>P. BOYLEN</b> |  |   |
| CHECKED BY:<br><b>J.S.H.</b>  |  |   |
| DATE:<br><b>11/30/00</b>      |  |   |
| SCALE:<br><b>1"=1000'</b>     |  |   |
| JOB NO.<br><b>644</b>         |  | <b>Southern</b><br><br><b>River Gas Corporation</b><br>Well# 29-455<br>Section 29, T15S, R10E, S.L.B.&M.<br>Carbon County, Utah |
| DRAWING NO.<br><b>A-1</b>     |  |   |
| SHEET <b>1</b> OF <b>4</b>    |  |   |

Phillips Petroleum Company  
USA 29-455  
Lease U-73075  
Drunkards Wash Unit  
NW/NW Section 29, T15S, R10E  
Carbon County, Utah

CONDITIONS OF APPROVAL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be advised that Phillips Petroleum is considered to be the operator of the above well and is responsible under the terms and conditions of the lease for the operations conducted on the leased lands.

Bond coverage for this well is provided by ES0048 (Principal - Phillips Petroleum Company) via surety consent as provided for in 43 CFR § 3104.2.

This office will hold the aforementioned operator and bond liable until the provisions of 43 CFR § 3106.7-2 continuing responsibility are met.

This permit will be valid for a period of one year from the date of approval. After permit termination, a new application must be filed for approval.

All lease operations will be conducted in full compliance with applicable regulations (43 CFR § 3100), Onshore Oil and Gas Orders, lease terms, notices to lessees, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions and the approved plan will be made available to field representatives to insure compliance.

#### A. DRILLING PROGRAM

1. The proposed BOPE is in a 2M configuration, and is adequate for this depth in this area. Installation, testing and operation of the system shall be in conformance with Onshore Oil and Gas Order No. 2.
2. The requirements for air drilling, found in Onshore Oil and Gas Order No. 2, part III, E (Special Drilling Operations), shall be followed. This section requires, at a minimum, the use of the following equipment not mentioned in the application:
  - Spark arresters
  - Blooie line discharge 100 feet from wellbore
  - Straight blooie line
  - Deduster equipment
  - Float valve above bit
  - Automatic igniter on the blooie line
3. Materials to counteract a gas kick shall be available on location.
4. As proposed, both casing strings shall be cemented back to surface. If cement behind the production (5½") casing does not circulate to surface, a Cement Bond Log or other appropriate tool shall be run to determine the depth to the top-of-cement.
5. Concurrent approval from the State of Utah, Division of Oil, Gas & Mining is required before conducting any surface disturbing activities.

**USA 29-455****B. SURFACE USE**

1. The following appendices are attached for your reference. They are to be followed as conditions of approval:  
  
**SM-1, Seed Mixture for Green Strip Areas**  
**SM-3, Seed Mixture for Salt Desert Areas**
2. Whether the mud pit shall be lined will be determined at the time of construction.
3. Within six months of installation, surface structures shall be painted in the following flat, earth tone color: Slate Grey (5Y 6/1). This Fuller O'Brien color is for reference only. Any brand of paint may be used provided the colors match. Any facilities that must be painted to comply with OSHA standards are exempt.

**GENERAL CONSTRUCTION**

1. Operator shall contact the Price BLM Office at least forty-eight hours prior to the anticipated start of construction and/or any surface disturbing activities. The BLM may require and schedule a preconstruction conference with the operator prior to the operator commencing construction and/or surface disturbing activities. The operator and the operator's contractor, or agents involved with construction and/or any surface disturbing activities associated with the project, shall attend this conference to review the Conditions of Approval and plan of development. The operator's inspector will be designated at the pre-drill conference, and is to be given an approved copy of all maps, permits and conditions of approval before the start of construction. The BLM will also designate a representative for the project at the preconstruction conference.
2. The operator shall designate a representative(s) who shall have the authority to act upon and to implement instructions from the BLM. The operator's representative shall be available for communication with the BLM within a reasonable time when construction or other surface disturbing activities are underway.
3. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the operator, or any person working on his behalf, on public land is to be immediately reported to the Price BLM Office. The operator will suspend all

operations in the immediate area of such discovery until written authorization to proceed is issued by the Price BLM Office. An evaluation of the discovery will be made by the BLM to determine appropriate actions to prevent the loss of significant cultural or scientific values. The operator is responsible for the cost of evaluation of any site found during construction. The BLM will determine what mitigation is necessary.

4. During project construction, surface disturbance and vehicle travel shall be limited to the approved location and access routes. Any additional area needed must be approved by the Price BLM Office prior to use.
5. The operator must provide a trash cage for the collection and containment of all trash. The trash shall be disposed in an authorized landfill. The location and access roads shall be kept litter free.
6. Vegetation removal necessitated by construction shall be confined to the limits of actual construction. Removed vegetation will be stockpiled for use in reclamation or removed from the construction site at the direction of the BLM.
7. Prior to surface disturbance, topsoil is to be separately removed and segregated from other material. Topsoil depth will be decided onsite by BLM. If the topsoil is less than 6 inches, a 6-inch layer that includes the A horizon and the unconsolidated material immediately below the A horizon shall be removed and the mixture segregated and redistributed as the surface soil layer.

Generally topsoil shall be stored within the pad site or adjacent to access roads. The company in consultation with BLM shall determine stockpile locations and dimensions at the onsite. If the topsoil stockpiles will not be redistributed for a period in excess of one (1) year, the stockpiles are to be seeded with seed mixture SM-3 (attached).

#### **ROAD and PIPELINE CONSTRUCTION**

8. Operator shall provide an inspector under the direction of a registered professional engineer (PE) at all times during road construction. A PE shall certify (statement with PE stamp) that the road was constructed to the required Bureau of Land Management (BLM) road standards.
9. Road construction or routine maintenance activities are to be performed during periods when the soil can adequately support construction equipment. If such equipment creates ruts more than 6 inches deep, the soil is deemed too wet to adequately support construction equipment.

10. The operator is responsible for maintenance of all roads authorized through the lease or a Right-of-Way. Construction and maintenance shall comply with Class II or III Road Standards as described in BLM Manual Section 9113 and the Moab District Road Standards, except as modified by BLM. Maintenance may include but is not limited to grading, applying gravel, snow removal, ditch cleaning, headcut restoration/prevention.
11. Topsoil from access roads and pipelines is to be wind rowed along the uphill side of the road or stored in an approved manner. When the road and pipeline is rehabilitated, this soil will then be used as a top coating for the seed bed.
12. Erosion-control structures such as water bars, diversion channels, and terraces will be constructed to divert water and reduce soil erosion on the disturbed area. Road ditch turnouts shall be equipped with energy dissipators as needed to avoid erosion. Where roads interrupt overland sheet-flow and convert this runoff to channel flow, ditch turnouts shall be designed to reconvert channel flow to sheet flow. Rock energy dissipators and gravel dispersion fans may be used, or any other design which would accomplish the desired reconversion of flow regime. As necessary cut banks, road drainages, and road crossings shall be armored or otherwise engineered to prevent headcutting.

### **PAD CONSTRUCTION**

13. During the construction of the drill pad, suitable topsoil material is to be stripped and conserved in a stockpile on the pad. If stockpiles are to remain for more than a year, they shall be seeded with the seed mixture in appendix SM-3, attached.
14. Generally, drill pads are to be designed to prevent overland flow of water from entering or leaving the site. The pad is to be sloped to drain spills and water into the reserve pit. The drill pad shall be designed to disperse diverted overland flow and to regulate flow velocity so as to prevent or minimize erosion. Well pad diversion outlets shall be equipped with rock energy brakes and gravel-bedded dispersion fans.

### **REHABILITATION PROCEDURES**

#### **Site Preparation**

15. The entire roadbed should be obliterated and brought back to the approximate original contour. Drainage control is to be reestablished as necessary. All areas affected by road construction are to be recontoured to blend in with the existing topography. All berms are to be removed unless determined to be beneficial by BLM. In recontouring the disturbed areas, care should be taken to not disturb additional vegetation.

#### Seedbed Preparation

16. An adequate seedbed should be prepared for all sites to be seeded. Areas to be revegetated should be chiseled or disked to a depth of at least 12 inches unless restrained by bedrock.
17. Ripping of fill materials should be completed by a bulldozer equipped with single or a twin set of ripper shanks. Ripping should be done on 4-foot centers to a depth of 12 inches. The process should be repeated until the compacted area is loose and friable, then shall be followed by final grading. Seedbed preparation will be considered complete when the soil surface is completely roughened and the number of rocks (if present) on the site is sufficient to cause the site to match the surrounding terrain.
18. After final grading, the stockpiled topsoil shall be spread evenly across the disturbed area.

#### Fertilization

19. Commercial fertilizer with a formula of 16-16-8 is to be applied at a rate of 200 pounds per acre to the site. The rate may be adjusted depending on soil.
20. Fertilizer is to be applied not more than 48 hours before seeding, and shall be cultivated into the upper 3 inches of soil.
21. Fertilizer is to be broadcast over the soil using hand-operated "cyclone-type" seeders or rotary broadcast equipment attached to construction or revegetation machinery as appropriate to slope. All equipment should be equipped with a metering device. Fertilizer application is to take place before the final seeding preparation treatment. Fertilizer broadcasting operations should not be conducted when wind velocities would interfere with even distribution of the material.

#### Mulching

22. When it is time to reclaim this location, the Price BLM Office will determine whether



it will be necessary to use mulch in the reclamation process. The type of mulch should meet the following requirements: Wood cellulose fiber shall be natural or cooked, shall disperse readily in water, and shall be nontoxic. Mulch shall be thermally produced and air dried. The homogeneous slurry or mixture shall be capable of application with power spray equipment. A colored dye that is noninjurious to plant growth may be used when specified. Wood cellulose fiber is to be packaged in new, labeled containers. A minimum application of 1500 pounds per acre shall be applied. A suitable tackifier shall be applied with the mulch at a rate of 60 to 80 pounds per acre.

An alternative method of mulching on small sites would be the application of straw or hay mulch at a rate of 2000 pounds per acre. Hay or straw shall be certified weed free. Following the application of straw or hay, crimping shall occur to ensure retention.

#### Reseeding

23. All disturbed areas are to be seeded with the seed mixture required by the BLM. The seed mixture(s) shall be planted in the fall of the year (Sept-Nov), in the amounts specified in pounds of pure live seed (PLS)/acre. There shall be no noxious weed seed in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within 12 months prior to planting. Commercial seed will be either certified or registered seed. The seed mixture container shall be tagged in accordance with State law(s) and available for inspection by the BLM. Seed is to be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture shall be evenly and uniformly planted over the disturbed area. (Smaller/heavier seeds tend to drop to the bottom of the drill and are planted first. Appropriate measures should be taken to ensure this does not occur.) Where drilling is not possible, seed is to be broadcast and the area raked or chained to cover the seed. Woody species with seeds that are too large for the drill will be broadcast. When broadcasting the seed, the pounds per acre noted below are to be increased by 50 percent. Reseeding may be required if a satisfactory stand is not established to the surface rights owner's specifications. Evaluation of the seeding's success will not be made before completion of the second growing season after the vegetation becomes established. The Price BLM Office is to be notified a minimum of seven days before seeding a project.
24. The disturbed areas for the road and pipeline must be seeded in the fall of the year, immediately after the topsoil is replaced. The prescribed seed mixture is attached as appendix SM-3.

**General**

25. Prior to the use of insecticides, herbicides, fungicides, rodenticides and other similar substances, the operator must obtain from BLM, approval of a written plan. The plan must describe the type and quantity of material to be used, the pest to be controlled, the method of application, the location for storage and disposal of containers, and other information that BLM may require. A pesticide may be used only in accordance with its registered uses and within other agency limitations. Pesticides must not be permanently stored on public lands.

## SM-1

## Green Strip Areas

The following seed mixture will be planted along service road borrow ditches, around the edge of drill pads with a production well, and surrounding other production and maintenance facilities. The purpose for this seeding is to provide a "green strip" buffer to minimize fire hazards and prevent invasion and establishment of noxious weeds in areas that will receive continued disturbance for the life of these project areas.

| <u>Common Plant Name</u> | <u>Scientific Name</u>                   | <u>Pounds per acre/PLS*</u> |
|--------------------------|--|-----------------------------|
| Forage kochia            | <u>Kochia prostrata</u>                  | 2                           |
| Wyoming big sagebrush    | <u>Artemisia tridentata wyomingensis</u> | 1                           |
|                          | Var. <u>Gordon Creek</u>                 |                             |
| Douglas low rabbitbrush  | <u>Chrysothamnus viscidiflorus</u>       | 1                           |
| Yellow sweetclover       | <u>Melilotus officinalis</u>             | 1                           |
| Small burnet             | <u>Sanguisorba minor</u>                 | 1                           |
| Bottlebrush squirreltail | <u>Elymus elymoides</u>                  | 1                           |
| Intermediate wheatgrass  | <u>Thinopyrum intermedium</u>            | 1                           |
|                          |  | <hr/>                       |
|                          | <b>Total</b>                             | <b>8</b>                    |

SM-3

**Salt Desert Areas****BLM SEED MIXTURES FOR THE PRICE COALBED METHANE PROJECT**

The following seed mixture is for areas that will receive final reclamation. Areas would be planted to protect them from soil erosion and to restore forage production.

NOTES: \_\_\_\_\_

| <u>Common Name</u>         | <u>Scientific Name</u>                   | <u>Pounds per acre/PLS</u> |
|----------------------------|--|----------------------------|
| <u>Grasses</u>             |  |                            |
| Indian rice grass          | <u>Oryzopsis hymenoides</u>              | 2                          |
| Squirreltail               | <u>Elymus elymoides</u>                  | 2                          |
| Galleta                    | <u>Hilaria jamesii</u>                   | 2                          |
| <u>Forbes</u>              |  |                            |
| Lewis flax                 | <u>Linum perenne lewisii</u>             | 1                          |
| Palmer penstemon           | <u>Penstemon palmerii</u>                | 1                          |
| Gooseberryleaf globemallow | <u>Sphaeralcea grossulariifolia</u>      | 0.5                        |
| <u>Shrubs</u>              |  |                            |
| Forage kochia              | <u>Kochia prostrata</u>                  | 2                          |
| Rubber rabbitbrush         | <u>Chrysothamnus nauseosus</u>           | 1                          |
| Fourwing saltbrush         | <u>Atriplex canescens</u>                | 2                          |
| Winterfat                  | <u>Krascheninnikovia (Eurotia) lanta</u> | 2                          |
| <b>Total</b>               |  | <b>15.5</b>                |

### C. REQUIRED APPROVALS, REPORTS AND NOTIFICATIONS

Required verbal notifications are summarized in Table 1, attached.

Building Location- Contact the Price Field Office, Natural Resource Protection Specialist at least 48-hours prior to commencing construction of location.

Spud- The spud date will be reported to BLM 24-hours prior to spudding. Written notification in the form of a Sundry Notice (Form 3160-5) will be submitted to the Moab Field Office within 24-hours after spudding, regardless of whether spud was made with a dry hole digger or big rig.

Daily Drilling Reports- Daily drilling reports shall detail the progress and status of the well and shall be submitted to the Moab Field Office on a weekly basis.

Monthly Reports of Operations- In accordance with Onshore Oil and Gas Order No. 1, this well shall be reported on Minerals Management Service (MMS) Form 3160, "Monthly Report of Operations," starting the month in which operations commence and continuing each month until the well is physically plugged and abandoned. This report will be filed directly with MMS.

Sundry Notices- There will be no deviation from the proposed drilling and/or workover program without prior approval. "Sundry Notices and Reports on Wells" (Form 3160-5) will be filed, with the Moab Field Office, for approval of all changes of plans and subsequent operations in accordance with 43 CFR § 3162.3-2. Safe drilling and operating practices must be observed.

Drilling Suspensions- Operations authorized by this permit shall not be suspended for more than 30 days without prior approval of the Moab Field Office. All conditions of this approval shall be applicable during any operations conducted with a replacement rig.

Undesirable Events- Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be immediately reported to the BLM in accordance with requirements of NTL-3A.

Cultural Resources- If cultural resources are discovered during construction, work that might disturb the resources is to stop, and the Price Field Office is to be notified.

First Production- Should the well be successfully completed for production, the Moab Field Office will be notified when the well is placed in producing status. Such notification may be made by phone, but must be followed by a sundry notice or letter not later than five business days following the date on which the well is placed into production.

A first production conference will be scheduled as soon as the productivity of the well is apparent. This conference should be coordinated through the Price Field Office. The Price Field Office shall be notified prior to the first sale.

Well Completion Report- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted to the Moab Field Office not later than thirty-days after completion of the well or after completion of operations being performed, in accordance with 43 CFR § 3162.4-1. Two copies of all logs, core descriptions, core analyses, well test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. When requested, samples (cuttings and/or samples) will be submitted to the Moab Field Office.

Venting/Flaring of Gas- Gas produced from this well may not be vented/flared beyond an initial, authorized test period of 30 days or 50 MMcf, whichever first occurs, without the prior, written approval of the Moab Field Office. Should gas be vented or flared without approval beyond the authorized test period, the well may be ordered shut-in until the gas can be captured or approval to continue the venting/flaring as uneconomic is granted. In such case, compensation to the lessor shall be required for that portion of the gas that is vented/flared without approval and which is determined to have been avoidably lost.

Produced Water- An application for approval of a permanent disposal method and location will be submitted to the Moab Field Office for approval pursuant to Onshore Oil and Gas Order No.7.

Off-Lease Measurement, Storage, Commingling- Prior approval must be obtained from the Moab Field Office for off-lease measurement, off-lease storage and/or commingling (either down-hole or at the surface).

Plugging and Abandonment- If the well is completed as a dry hole, plugging instructions must be obtained from the Moab Field Office prior to initiating plugging operations.

A "Subsequent Report of Abandonment" (Form 3160-5) will be filed with the Moab Field Office within thirty-days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Upon completion of approved plugging, a regulation marker will be erected in accordance with 43 CFR § 3162.6. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the Price Field Office or the appropriate surface managing agency.

TABLE 1

NOTIFICATIONS

Notify Don Stephens ( work: 435-636-3608, home: 435-637-7967) or Mike Kaminski (work: 435-636-3640, home: 435-637-2518) of the BLM, Price Field Office for the following:

2 days prior to commencement of dirt work, construction and reclamation;

1 day prior to spudding;

50 feet prior to reaching the surface casing setting depth.

If the people at the above numbers cannot be reached, notify the Moab Field Office at (435) 259-2100. If unsuccessful, contact the person listed below.

Well abandonment operations require 24 hour advance notice and prior approval. In the case of newly drilled dry holes, verbal approval can be obtained by calling the Moab Field Office at (435) 259-2100. If approval is needed after work hours, you may contact the following:

|                                |                        |
|--------------------------------|------------------------|
| Eric Jones, Petroleum Engineer | Office: (435) 259-2117 |
|                                | Home: (435) 259-2214   |



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT


Utah State Office  
P.O. Box 45155  
Salt Lake City, UT 84145-0155

IN REPLY REFER TO  
UT-931

# CONFIDENTIAL

April 10, 2001

Phillips Petroleum Company  
c/o Pruitt, Gushee & Bachtell  
Attn: Fred MacDonald  
Suite 1850 Beneficial Life Tower  
Salt Lake City, Utah 84111-1495



Gentlemen:

Enclosed is one approved copy of Communitization Agreement No. UTU79452. This agreement communitizes all rights as to natural gas and associated liquid hydrocarbons producible from the Ferron Formation, covering the NW¼ of Section 29, Township 15 South, Range 10 East, SLB&M, Carbon County, Utah. This agreement conforms with the spacing set forth in Order No. 137-2(B) which was issued by the State of Utah, Board of Oil, Gas and Mining on February 25, 1982.

This agreement is effective as of April 1, 2001. The communitized area covers 160.00 acres and includes portions of Federal oil and gas lease UTU73075.

Approval of this agreement does not warrant or certify that the operator thereof and other holders of operating rights hold legal or equitable title to those rights in the subject leases which are committed hereto.

Minerals Management Service Form MMS-3160, "Monthly Report of Operations", must be submitted for this agreement beginning with the month in which drilling operations commence for Well No. 29-455, NW¼NW¼ Section 29, Township 15 South, Range 10 East, SLB&M, Carbon County, Utah, API # 43-007-30507, on Lease No. UTU73075. Form MMS-3160 is to be mailed to the Minerals Management Service, Production Accounting Division, P. O. Box 17110, Denver, Colorado 80217.

If this well is producing, this approval requires the submission of a Payor Information Form MMS-4025 to the Minerals Management Service (MMS) within 30 days (30 CFR 210.51). Please notify the designated payor or payors (purchasers, working interest owners, or others) as soon as possible regarding this requirement. Any production royalties that are due must be reported and paid within 90 days of the Bureau of Land Management's approval date or the payors will be assessed interest for late payment under the Federal Oil and Gas Royalty Management Act of 1982 (See 30 CFR 218.54). If you need assistance or clarification, please contact the Minerals Management Service at 1-800-525-9167 or 303-231-3504.



Please furnish all interested principals with necessary evidence of this approval.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks  
Chief, Branch of Fluid Minerals

Enclosure

bcc: Mineral Adjudication Group w/enclosure  
Field Manager - Moab w/enclosure  
Division Oil, Gas & Mining  
File - UTU79452  
MMS - Data Management Division  
Agr. Sec. Chron.  
Fluid Chron.

UT931:TATHOMPSON:tt:4/10/01

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.  
Use "APPLICATION FOR PERMIT--" for such proposals

*SUBMIT IN TRIPLICATE*

**CONFIDENTIAL**

1. Type of Well  
☐ Oil ☒ Gas ☐

2. Name of Operator

Phillips Petroleum Company

3. Address and Telephone No.

6825 S. 5300 W. P.O. Box 851 Price, Utah 84501 (435) 613-9777

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

940' FNL, 789' FWL  
NW/4,NW/4, Sec.29, T15S,R10E, SLB&M

5. Lease Designation and Serial No.

UTU-73075

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

Drunkards Wash UTU-67921X

8. Well Name and No.

USA 29-455

9. API Well No.

43-007-30507

10. Field and Pool, or Exploratory Area

Drunkards Wash

11. County or Parish, State

Carbon County, Utah

12. **CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

| TYPE OF SUBMISSION                                | TYPE OF ACTION                                  |  |
|---|---|--|
| <input type="checkbox"/> Notice of Intent         | <input checked="" type="checkbox"/> Well Report | <input type="checkbox"/> Change of Plans         |
| <input type="checkbox"/> Subsequent Report        | <input type="checkbox"/> Change of Name         | <input type="checkbox"/> New Construction        |
| <input type="checkbox"/> Final Abandonment Notice | <input type="checkbox"/> Recompletion           | <input type="checkbox"/> Non-Routine Fracturing  |
|   | <input type="checkbox"/> Plugging Back          | <input type="checkbox"/> Water Shut-Off          |
|   | <input type="checkbox"/> Casing Repair          | <input type="checkbox"/> Conversion to Injection |
|   | <input type="checkbox"/> Altering Casing        | <input type="checkbox"/> Dispose Water           |
|   | Other _____                                     |  |

13. Describe Proposed or Completed Operations ( Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

See Attached.

**COPY**

14. I hereby certify that the foregoing is true and correct

Signed Charles H. Hannon

Title Administrative Assistant

Date 4/20/01

(This space for Federal or State office use)

Approved by \_\_\_\_\_ Title \_\_\_\_\_ Date \_\_\_\_\_  
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

# DRUNKARDS WASH PROJECT

## DAILY WELL REPORT

USA

29-455

API NO: 43-007-30507

940 FNL, 789 FWL

NWNW SEC: 29 TWN: 15S RNG: 10E

COUNTY: Carbon

ELEVATION: 5718

DRILLING CONTRACTOR: Pense Brothers Rig #9

SPUD TIME/DATE: 4/12/01 11:00:00 AM

TD TIME/DATE: 4/13/01 9:45:00 AM

TD DEPTH: 1700

ON-LINE TIME/DATE:

### Bit Information

| Type       | Size  | In     | Out     | Hours | Rotating Hours |
|------------|-------|--------|---------|-------|----------------|
| Air Hammer | 15 in | 0.00   | 6.00    | 0.5   | 0.25           |
| Air Hammer | 11 in | 6.00   | 180.00  | 2     | 1.5            |
| Air Hammer | 7 7/8 | 180.00 | 1700.00 | 11    | 7              |

### Conductor Casing

Bore Hole Size: 15 in Conductor From: 0.00 To: 6.00

Casing Description: 12 3/4 in PE Number of Joints: 1 Set @: 6.00

Cement: Amount:

Cement Report:

### Surface Casing

Bore Hole Size: 11 in Surface Casing From: 6.00 To: 180.00

Casing Description: 8 5/8 in 24#/ft J-55 Number of Joints: 6 Set @: 174.30

Cement: G + 2%S-1 + 1/4#/sk D-29 Amount: 100.00

Cement Report: r/up cementers, safety meeting, test lines, pump 15bbl h2o ahead, mix &amp; pump 100 sks cement, displace w/ 9bbl h2o, close valve @ 4pm 4/12/01, 7 bbl good cement to surface,

### Production Casing

Bore Hole Size: 7 7/8 in Prod.Casing From: 174.00 To: 1700.00

Casing Description: 5 1/2 in 17#/ft N-80 Number of Joints: 39 Length: 1664.00

Lead Cement: 50/50 POZ, 8%D20, 10%D44, 2%S001, 1/4#/sk Amount: 150.00  
D29

Tail Cement: 10-1 RFC Amount: 60.00

Cement Report: r/up cementers, safety meeting, test lines, wash down 1jt of csg, circulate bottoms up, r/up cement head, test lines, break circulaion, circulate &amp; get good rate, mix &amp; pump 150sks lead, 60sks tail, s/down &amp; drop plug, displace w/ 39 bbls h2o, plug down @ 1:15pm 4/14/01, 6bbl good cement to surface, r/down cementers,

Float Equipment: Centralizers ran on:

CONFIDENTIAL

## Drilling Data

**DAY 1 4/13/01**

CURRENT DEPTH: 1130 CURRENT OPERATIONS: drilling 7 7/8in hole @ 1130ft, ROTATING HRS: 6.00

7am-10am mov on location, 10am-11am r/up & service equipment, 11am-12pm spud @ 11am 4/12/01, drill & set 6ft of 12 3/4in conductor, 12pm-1pm n/up to drill 11in hole, 1pm-2:30pm drill 180ft 11in hole, 2:30pm-3pm clean hole & tooh, 3pm-3:30pm rih w/ 8 5/8in guide shoe + 6 jts of 8 5/8in csg, land csg @ 174.3ft, 3:30pm-4pm r/up cementers, cement surface pipe, close valve @ 4pm 4/12/01, 7bbl good cement to surface, 4pm-9pm woc, 9pm-12am break loose, n/up bope & manifold, 12am-2am test bope (had to re-tighten flange bolts), 2am-3am n/up, rih, drill out cement, 3am-4am drilling 7 7/8in hole, 450ft @ 4am, 4am-5am drill 450-710ft, 5am-6am drill 710-920ft, 6am-7am drill 920-1130ft,

**DAY 2 4/14/01**

CURRENT DEPTH: 1700 CURRENT OPERATIONS: r/up to run casing ROTATING HRS: 2.75

7am-8am drill 1130-1370ft, 8am-9am drill 1370-1550ft, 9am-9:45am drill 1550-1700ft, td @ 9:45am 4/13/01, 9:45am-10:15am clean hole, 10:15am-10:30am start pooh, hydraulic wrench broke s/down to repair, 10:30am-12pm repair wrench, 12pm-1:20pm finish pooh, lay hammer down, 1:20pm-4pm r/up loggers, log well, 4pm-4:30pm r/down loggers, release rig @ 4:30pm 4/13/01, 4:30pm-7pm moving off location, 7pm-7am no activity,

**DAY 3 4/15/01**

CURRENT DEPTH: 1634 CURRENT OPERATIONS: no activity ROTATING HRS: 0.00

7am-8:30am r/up workover rig & set pipe racks, 8:30am-9:30am unload csg, remove thread protectors, & tally pipe, 9:30am-11:30am rih w/ 5 1/2in float shoe + 39 jts 5 1/2in csg, tagged fill on last joint @ 1620ft, 11:30am-12:45pm r/up cementers to wash down csg, wash jt down, land csg @ 1664ft, circulate bottoms up s/down & r/up cement head, 12:45pm-1:15pm cement longstring, plug down @ 1:15pm 4/14/01, 6bbl good cement to surface, 1:15pm-2pm r/down cementers, sdfn

**DAY 4 4/16/01**

CURRENT DEPTH: 1664 CURRENT OPERATIONS: making scraper run ROTATING HRS: 0.00

7am-7am no activity

**DAY 5 4/17/01**

CURRENT DEPTH: 1664 CURRENT OPERATIONS: no activity ROTATING HRS: 0.00

7am-12pm n/down bope, n/up wellhead, change over to run tbq, rih w/ 4 3/4in nom csg scraper + 52 jts tbq, tag @ 1663ft, pooh laying tbq down on trailer, r/down & move off location

## Frac Data

## Completion Data

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.  
Use "APPLICATION FOR PERMIT--" for such proposals

*SUBMIT IN TRIPLICATE*

1. Type of Well  
☐ Oil ☒ Gas ☐ Other

CONFIDENTIAL

2. Name of Operator  
Phillips Petroleum Company

3. Address and Telephone No.  
6825 S. 5300 W. P.O. Box 851 Price, Utah 84501 (435) 613-9777

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
940' FNL, 789' FWL  
NW/4, NW/4, Sec.29, T15S, R10E,SLB&M

5. Lease Designation and Serial No.  
UTU-73075

6. If Indian, Allottee or Tribe Name  
N/A

7. If Unit or CA, Agreement Designation  
Drunkards Wash UTU-67921X

8. Well Name and No.  
USA 29-455

9. API Well No.  
43-007-30507

10. Field and Pool, or Exploratory Area  
Drunkards Wash

11. County or Parish, State  
Carbon County, Utah

12. **CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

| TYPE OF SUBMISSION                                | TYPE OF ACTION                                  |  |
|---|---|--|
| <input type="checkbox"/> Notice of Intent         | <input checked="" type="checkbox"/> Spud Notice | <input type="checkbox"/> Change of Plans         |
| <input type="checkbox"/> Subsequent Report        | <input type="checkbox"/> Change of Name         | <input type="checkbox"/> New Construction        |
| <input type="checkbox"/> Final Abandonment Notice | <input type="checkbox"/> Recompletion           | <input type="checkbox"/> Non-Routine Fracturing  |
|   | <input type="checkbox"/> Plugging Back          | <input type="checkbox"/> Water Shut-Off          |
|   | <input type="checkbox"/> Casing Repair          | <input type="checkbox"/> Conversion to Injection |
|   | <input type="checkbox"/> Altering Casing        | <input type="checkbox"/> Dispose Water           |
|   | Other _____                                     |  |

13. Describe Proposed or Completed Operations ( Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Please be advised that the USA 29-455 well was spud on 4/12/01 at 11:00 am  
Pense Bros. Rig #9  
Dry Drill

ORIGINAL

14. I hereby certify that the foregoing is true and correct

Signed Frankie Hathaway Title Administrative Assistant Date 4/20/01

(This space for Federal or State office use)

Approved by \_\_\_\_\_ Title \_\_\_\_\_ Date \_\_\_\_\_  
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING  
ENTITY ACTION FORM - FORM 6

OPERATOR Phillips Petroleum Company  
ADDRESS 6825 S. 5300 W. P.O. Box 851  
Price, UT 84501

OPERATOR ACCT. NO. 1475

| ACTION CODE  | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER               | WELL NAME              | WELL LOCATION |               |     |                |        | SPUD DATE | EFFECTIVE DATE |
|--|--------------------|----------------|--------------------------|------------------------|---------------|---------------|-----|----------------|--------|-----------|----------------|
|  |                    |                |                          |                        | QQ            | SC            | TP  | RG             | COUNTY |           |                |
| AR   | 99999              | 13110          | 43-007-30507             | USA 29-455             | NWNW          | 29            | 15S | 10E            | Carbon | 04/12/01  |                |
| WELL 1 COMMENTS: New single well, new spud outside PA but inside of Unit boundary<br>5-2-01 <div style="text-align: right; font-size: 2em; opacity: 0.5;">CONFIDENTIAL</div>   |                    |                |                          |                        |               |               |     |                |        |           |                |
| AR   | 99999              | 13111          | 43-007-30518             | RGC 28-319             | NENW          | 28            | 15S | 09E            | Carbon | 04/13/01  |                |
| WELL 2 COMMENTS: New single well, new spud outside PA but inside of Unit boundary<br>5-2-01 <div style="text-align: right; font-size: 2em; opacity: 0.5;">CONFIDENTIAL</div>   |                    |                |                          |                        |               |               |     |                |        |           |                |
| AR   | 99999              | 13112          | 43-007-30722             | Utah 09-453            | NWSE          | 09            | 15S | 10E            | Carbon | 04/17/01  |                |
| WELL 3 COMMENTS: New single well, new spud outside PA but inside of Unit boundary<br>5-2-01 <div style="text-align: right; font-size: 2em; opacity: 0.5;">CONFIDENTIAL</div>   |                    |                |                          |                        |               |               |     |                |        |           |                |
| AR   | 99999              | 13113          | 43-007-30560             | Utah 28-321            | NESE          | 28            | 15S | 09E            | Carbon | 04/19/01  |                |
| WELL 4 COMMENTS: New single well, new spud outside PA but inside of Unit boundary<br>5-2-01 <div style="text-align: right; font-size: 2em; opacity: 0.5;">CONFIDENTIAL</div>   |                    |                |                          |                        |               |               |     |                |        |           |                |
| AR   | 99999              | 13114          | 43-007- <del>30576</del> | RGC <del>28</del> -332 | SWSE          | <del>28</del> | 15S | <del>09E</del> | Carbon | 04/22/01  |                |
| WELL 5 COMMENTS: <span style="margin-left: 100px;">30743</span> <span style="margin-left: 100px;">21-332</span> <span style="margin-left: 100px;">21 15S 09E</span><br>New single well, new spud outside PA but inside of Unit boundary<br>5-2-01 <div style="text-align: right; font-size: 2em; opacity: 0.5;">CONFIDENTIAL</div> |                    |                |                          |                        |               |               |     |                |        |           |                |

ACTION CODES (See Instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

Frankie Hathaway  
Signature

Administrative Assistant 5/2/01  
Title Date

Phone No. (435)613-9777

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE  
(See other In-  
structions on  
reverse side)

Form approved.  
Budget Bureau No. 1004-0137  
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG\*

|   |   |   |   |
|---|---|---|---|
| 1a. TYPE OF WELL:<br>OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> Other _____  |   | 5. LEASE DESIGNATION AND SERIAL NO.<br>UTU - 73075  |   |
| b. TYPE OF COMPLETION:<br>NEW WELL <input checked="" type="checkbox"/> WORK OVER <input type="checkbox"/> DEEP-EN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> Other _____ |   | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME<br>N/A   |   |
| 2. NAME OF OPERATOR<br>Phillips Petroleum Company   |   | 7. UNIT AGREEMENT NAME<br>Drunkards Wash UTU-67921X   |   |
| 3. ADDRESS OF OPERATOR<br>6825 S. 5300 W. P.O. Box 851 Price, Utah 84501 (435) 613-9777   |   | 8. FARM OR LEASE NAME<br>USA  |   |
| 4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)<br>At surface 940' FNL, 789' FWL<br>At top prod. interval reported below<br>At total depth  |   | 9. WELL NO.<br>29-455   |   |
| 10. FIELD AND POOL, OR WILDCAT<br>Drunkards Wash  |   | 11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA<br>NW/NW, Sec. 29, T15S, R10E, SLB&M  |   |
| 14. PERMIT NO.<br>43-007-30507  |   | DATE ISSUED<br>1/8/01   |   |
| 15. DATE SPUDDED<br>4/12/01   |   | 16. DATE T.D. REACHED<br>4/13/01  |   |
| 17. DATE COMPL. (Ready to prod.)<br>5/4/01  |   | 18. ELEVATIONS (DF, REB, RT, GR, ETC.)<br>5718' GR  |   |
| 19. ELEV. CASINGHEAD<br>N/A   |   | 12. COUNTY<br>Carbon  |   |
| 13. STATE<br>UTAH   |   | 20. TOTAL DEPTH, MD & TVD<br>1700'  |   |
| 21. PLUG BACK T.D., MD & TVD<br>1664'   |   | 22. IF MULTIPLE COMPL. HOW MANY<br>N/A  |   |
| 23. INTERVALS DRILLED BY<br>ROTARY TOOLS to TD  |   | CABLE TOOLS   |   |
| 24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD OR TVD)<br>Ferron Coal- Top Coal 1363' & Bottom Coal 1508'   |   | 25. WAS DIRECTIONAL SURVEY MADE<br>NO   |   |
| 26. TYPE ELECTRIC AND OTHER LOGS RUN<br>CBL/LCL/GR-5-7-01<br>Dual Induct. Laterolog, CBL, Spect. Litho Dens. Comp. Neut. GR log 5-7-01  |   | 27. WAS WELL CORED<br>No  |   |
| 28. CASING RECORD (Report all strings set in well)  |   |   |   |
| CASING SIZE   | WEIGHT, LB./FT.   | DEPTH SET (MD)  | HOLE SIZE                                       |
| 12-3/4"   | Conductor PE  | 6'  | 15"   |
| 8-5/8"  | 55 24#  | 174.3'  | 11"   |
| 5-1/2"  | 158 17#   | 1664'   | 7-7/8"  |
| 29. LINER RECORD  |   | 30. TUBING RECORD   |   |
| SIZE  | TOP (MD)  | BOTTOM (MD)   | SACKS CEMENT                                    |
|   |   |   | SCREEN (MD)                                     |
|   |   |   | SIZE  |
|   |   |   | DEPTH SET (MD)                                  |
|   |   |   | PACKER SET                                      |
| 31. PERFORATION RECORD (Interval, size and number)<br>Ferron Coal:<br>Upper: 1363'-1380', 1394'-1402'<br>Lower: 1470'-1475', 1484'-1486', 1490'-1508'<br>4spf. 88"<br>4spf. 88"   |   | 32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.<br>DEPTH INTERVAL (MD)<br>Upper: 1363'-1402'<br>Lower: 1470'-1508'<br>AMOUNT AND KIND OF MATERIAL USED<br>100,000#, 16/30; 32,232 gal fluid<br>110,000#, 16/30; 36,269 gal fluid |   |
| 33. PRODUCTION  |   |   |   |
| DATE FIRST PRODUCTION<br>5/10/01  | PRODUCTION METHOD (Flowing, gas lift, pumping---size and type of pump)<br>Pumping 2-1/2x2x16 RWAC |   | WELL STATUS (Producing or shut-in)<br>Producing |
| DATE OF TEST<br>05/10/01  | HOURS TESTED<br>24  | CHOKE SIZE<br>N/A   | PROD'N FOR TEST PERIOD<br>N/A                   |
| FLOW. TUBING PRESS.<br>0  | CASING PRESSURE<br>0  | CALCULATED 24-HOUR RATE<br>N/A  | OIL---BBL.<br>N/A                               |
| 34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)<br>SOLD  |   | TEST WITNESSED BY<br>Jerry H. Dietz   |   |
| 35. LIST OF ATTACHMENTS   |   |   |   |
| 36 I hereby certify that the foregoing and attached information is complete and correct as determined from all available records<br>SIGNED Jean Semborski TITLE Permit Specialist DATE 05/16/01                                 |   |   |   |

WELL NUMBER: USA 29-455

| 37 SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof, cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries): |       |        |                             | 38. GEOLOGIC MARKERS |                 |                  |
|---|-------|--------|-----------------------------|----------------------|-----------------|------------------|
| FORMATION   | TOP   | BOTTOM | DESCRIPTION, CONTENTS, ETC. | NAME                 | TOP MEAS. DEPTH | TRUE VERT. DEPTH |
| Ferron  | 1471' | 1495'  | Coals and Sandstones        | Blue Gate            | NR              |                  |
|   |       |        | Coal Interval: 1471'-1495'  | Bentonite            |                 |                  |
|   |       |        |                             | Tununk Shale         | 1595'           |                  |
|   |       |        |                             | Ferron Sandston      | 1360'           |                  |



STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

ORIGINAL CONFIDENTIAL

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☐ GAS ☒ OTHER:

2. Name of Operator:

Phillips Petroleum Company

3. Address and Telephone Number:

6825 South 5300 West, P.O. Box 851, Price, UT 84501 (435) 613-9777

4. Location of Well  
Footages:

940' FNL, 789' FWL

QQ, Sec., T., R., M.:

NW/NW, SEC. 29, T15S, R10E, SLB & M

5. Lease Designation and Serial Number:

U - 73075

6. If Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

UTU67921X Drunkards Wash

8. Well Name and Number:

USA 29-455

9. API Well Number:

43-007-30507

10. Field or Pool, or Wildcat:

Drunkards Wash

County: Carbon County

State: Utah

**11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

**NOTICE OF INTENT**  
(Submit in Duplicate)

- |  |  |
|--|--|
| <input type="checkbox"/> Abandon                   | <input type="checkbox"/> New Construction  |
| <input type="checkbox"/> Repair Casing             | <input type="checkbox"/> Pull or Alter Csg |
| <input type="checkbox"/> Change of Plans           | <input type="checkbox"/> Recomplete        |
| <input type="checkbox"/> Convert to Injection      | <input type="checkbox"/> Reperforate       |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare     |
| <input type="checkbox"/> Multiple Completion       | <input type="checkbox"/> Water Shut-Off    |
| <input type="checkbox"/> Other _____               |  |
| Approximate date work will start _____             |  |

**SUBSEQUENT REPORT**  
(Submit Original Form Only)

- |   |  |
|---|--|
| <input type="checkbox"/> Abandon *  | <input type="checkbox"/> New Construction  |
| <input type="checkbox"/> Repair Casing                                    | <input type="checkbox"/> Pull or Alter Csg |
| <input type="checkbox"/> Change of Plans                                  | <input type="checkbox"/> Reperforate       |
| <input type="checkbox"/> Convert to Injection                             | <input type="checkbox"/> Vent or Flare     |
| <input type="checkbox"/> Fracture Treat or Acidize                        | <input type="checkbox"/> Water Shut-Off    |
| <input checked="" type="checkbox"/> Other <u>Chemical/Flush Treatment</u> |  |
| Date of work completion <u>06/18/2001</u>                                 |  |

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

\* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please be advised that the above referenced well was chemically treated with 4,000 gallons of low Ph fluid & 250 gallons of 7 1/2% HCL on 06/18/01.

RECEIVED

JUL 12 2001

DIVISION OF  
OIL GAS AND MINING

13.

Name & Signature:

Rochelle Crabtree

*Rochelle Crabtree*

Title:

Administrative Assistant

Date:

06/25/2001

(This space for state use only)

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

|   |  |   |
|---|--|---|
| 1. TYPE OF WELL<br>OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>All</u> |  | 5. LEASE DESIGNATION AND SERIAL NUMBER:       |
| 2. NAME OF OPERATOR:<br>Phillips Petroleum Company  |  | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME:         |
| 3. ADDRESS OF OPERATOR:<br>980 Plaza Office CITY Bartlesville STATE OK ZIP 74004                        |  | 7. UNIT or CA AGREEMENT NAME:                 |
| PHONE NUMBER:<br>(918) 661-4415   |  | 8. WELL NAME and NUMBER:<br>See Attached List |
| 4. LOCATION OF WELL<br>FOOTAGES AT SURFACE: See Attached List   |  | 9. API NUMBER:<br>See List                    |
| QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:  |  | 10. FIELD AND POOL, OR WILDCAT:               |
|   |  | COUNTY:                                       |
|   |  | STATE: UTAH                                   |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


| TYPE OF SUBMISSION  | TYPE OF ACTION  |   |  |
|---|---|---|--|
| <input type="checkbox"/> NOTICE OF INTENT<br>(Submit in Duplicate)<br>Approximate date work will start:<br>_____          | <input type="checkbox"/> ACIDIZE                        | <input type="checkbox"/> DEEPEN                           | <input type="checkbox"/> REPERFORATE CURRENT FORMATION |
|   | <input type="checkbox"/> ALTER CASING                   | <input type="checkbox"/> FRACTURE TREAT                   | <input type="checkbox"/> SIDETRACK TO REPAIR WELL      |
|   | <input type="checkbox"/> CASING REPAIR                  | <input type="checkbox"/> NEW CONSTRUCTION                 | <input type="checkbox"/> TEMPORARILY ABANDON           |
|   | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS       | <input checked="" type="checkbox"/> OPERATOR CHANGE       | <input type="checkbox"/> TUBING REPAIR                 |
|   | <input type="checkbox"/> CHANGE TUBING                  | <input type="checkbox"/> PLUG AND ABANDON                 | <input type="checkbox"/> VENT OR FLARE                 |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT<br>(Submit Original Form Only)<br>Date of work completion:<br>_____ | <input type="checkbox"/> CHANGE WELL NAME               | <input type="checkbox"/> PLUG BACK                        | <input type="checkbox"/> WATER DISPOSAL                |
|   | <input type="checkbox"/> CHANGE WELL STATUS             | <input type="checkbox"/> PRODUCTION (START/RESUME)        | <input type="checkbox"/> WATER SHUT-OFF                |
|   | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE         | <input type="checkbox"/> OTHER: _____                  |
|   | <input type="checkbox"/> CONVERT WELL TYPE              | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION |  |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


Conoco Inc. was merged into Phillips Petroleum Company, the surviving corporation, on December 31, 2002. In connection with this merger and effective on the same date, the name of the surviving corporation was changed to "ConocoPhillips Company". We are requesting that a new Operator Number be assigned to ConocoPhillips Company.

Please send production reporting forms to Herb Henderson at ConocoPhillips Company, 315 S. Johnstone, 980 Plaza Office, Bartlesville, OK 74004. Herb's phone number is 918-661-4415.

Current Operator  
Phillips Petroleum Company

  
Steve de Albuquerque


New Operator  
ConocoPhillips Company

  
Yolanda Perez

RECEIVED

JAN 08 2003

DIV. OF OIL, GAS & MINING

|   |                                     |
|---|-------------------------------------|
| NAME (PLEASE PRINT) <u>Yolanda Perez</u>  | TITLE <u>Sr. Regulatory Analyst</u> |
| SIGNATURE  | DATE <u>12/30/2002</u>              |

(This space for State use only)



Re: Notice of Address Change, Merger and Name Change  
Address Change effective **December 2, 2002**  
Merger and Name Change effective **December 31, 2002**

Divisions of Oil, Gas, and Mining  
Attn: Mr. John Baza  
1594 West North Temple,  
Suite 1210, P. O. Box 145801  
Salt Lake City, UT 84114-5801

Gentlemen:

1. Effective December 2, 2002, Phillips Petroleum Company will close its Englewood, Colorado Rocky Mountain Region office. After that time, all correspondence, notices and invoice for Land related matters should be directed to the address(es) noted below. Note that until December 31, 2002, all properties in which Phillips held an interest will continue to be operated by Phillips Petroleum Company, a wholly-owned subsidiary of ConocoPhillips.

2. On December 31, 2002, Phillips Petroleum Company and Conoco Inc. will merge, and the surviving corporation will be renamed "ConocoPhillips Company".

In accordance with the notice provisions of the Operating Agreements and other agreements, if any, between our companies, please adjust your company/organization records, effective for address purposes as of December 2, 2002, and for company name purposes, as of January 1, 2003, to reflect the following information for addressing and delivery of notices, invoicing and payment, and communications with ConocoPhillips Company. This will also apply to Lease Sale notices and other lease-related correspondence and notifications.

**U.S. Mail Address:**

ConocoPhillips Company  
P.O. Box 2197  
Houston, Texas 77252  
Attn: Chief Landman,  
San Juan/Rockies

**Physical Address & Overnight Delivery:**

ConocoPhillips Company  
550 Westlake Park Blvd.  
Three Westlake Park  
3WL, Room WL 9000  
Houston, Texas 77079  
Attn: Chief Landman,  
San Juan/Rockies

**All ballots and official notices/responses sent by facsimile transmission should be sent to the following contact:**

Attn: Chief Landman,  
San Juan/Rockies

Fax No.: 832-486-2688 or  
832-486-2687

Please contact the undersigned immediately if you have any questions. This notice does not apply to royalty inquiries, joint interest billings, or revenue remittances. Please continue to use the same addresses you are currently using for these matters

Sincerely,

**RECEIVED**

DEC 02 2002

DIVISION OF  
OIL, GAS AND MINING



## SECRETARY'S CERTIFICATE

I, the undersigned, Jennifer M. Garcia, Assistant Secretary of ConocoPhillips Company, formerly Phillips Petroleum Company, organized and existing under and by virtue of the laws of the State of Delaware (the "Corporation"), hereby certify that:

1. As Assistant Secretary I am authorized to execute this certificate on behalf of the Corporation.
2. The attached photocopy of the Certificate of Amendment to the Restated Certificate of Incorporation of Phillips Petroleum Company (to be renamed ConocoPhillips Company) is a true and correct copy as filed in the office of the Secretary of State of Delaware on the 12<sup>th</sup> day of December 2002, with an effective date of January 1, 2003 and such Certificate of Amendment has not been modified, amended, rescinded or revoked and is in full force and effect as of the date hereof.
3. The attached photocopy of the Certificate of Merger of Conoco Inc. with and into ConocoPhillips Company is a true and correct copy as filed in the office of the Secretary of State of Delaware on the 12<sup>th</sup> day of December 2002, with an effective date of December 31, 2002 and such Certificate of Merger has not been modified, amended, rescinded or revoked and is in full force and effect as of the date hereof.

IN WITNESS WHEREOF, I have hereunto set my hand as Assistant Secretary and affixed the corporate seal of the Corporation this 7th day of January 2003.


  
Assistant Secretary  
ConocoPhillips Company

STATE OF TEXAS           §  
                                     §  
COUNTY OF HARRIS   §

This instrument was acknowledged before me on January 7, 2003, by Jennifer M. Garcia, Assistant Secretary of ConocoPhillips Company, a Delaware corporation, on behalf of said Corporation.



RECEIVED  
JAN 08 2003

  
Notary Public

DIV. OF OIL, GAS & MINING

# Delaware

PAGE 1

*The First State*


I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "PHILLIPS PETROLEUM COMPANY", CHANGING ITS NAME FROM "PHILLIPS PETROLEUM COMPANY" TO "CONOCOPHILLIPS COMPANY", FILED IN THIS OFFICE ON THE TWELFTH DAY OF DECEMBER, A.D. 2002, AT 1:41 O'CLOCK P.M. ---

AND I DO HEREBY FURTHER CERTIFY THAT THE EFFECTIVE DATE OF THE AFORESAID CERTIFICATE OF AMENDMENT IS THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2002, AT 11 O'CLOCK P.M.

RECEIVED

JAN 08 2003

DIV. OF OIL, GAS & MINING



0064324 8100

030002793

*Harriet Smith Windsor*  
Harriet Smith Windsor, Secretary of State

AUTHENTICATION: 2183360

DATE: 01-02-03

FROM RL&F#1

(THU) 12.12.02 13:32/ST. 13:34:48/ST. 13:34:48/ST. 13:34:48/ST. 13:34:48/ST. 5  
STATE OF DELAWARE  
SECRETARY OF STATE  
DIVISION OF CORPORATIONS  
FILED 01:41 PM 12/12/2002  
020763238 - 0064324

## **CERTIFICATE OF AMENDMENT**

to the

## **RESTATED CERTIFICATE OF INCORPORATION**

of

### **PHILLIPS PETROLEUM COMPANY (to be renamed ConocoPhillips Company)**

Phillips Petroleum Company ("Phillips"), a corporation organized and existing under the General Corporation Law of the State of Delaware (the "DGCL"), hereby certifies that:

1. The amendments to Phillips' Restated Certificate of Incorporation set forth below were duly adopted in accordance with the provisions of Section 242 of the DGCL and have been consented to in writing by the sole stockholder of Phillips in accordance with Section 228 of the DGCL.

2. Phillips' Restated Certificate of Incorporation is hereby amended by deleting Article I thereof and replacing in lieu thereof a new Article I reading in its entirety as follows:

"The name of the corporation (which is hereinafter referred to as the "Corporation") is ConocoPhillips Company."

3. Phillips' Restated Certificate of Incorporation is hereby amended by deleting Section 1 of Article IV thereof and replacing in lieu thereof a new Section 1 reading in its entirety as follows:

"Section 1. The Corporation shall be authorized to issue 2,100 shares of capital stock, of which 2,100 shares shall be shares of Common Stock, \$.01 par value ("Common Stock")."

4. Pursuant to Section 103(d) of the DGCL, this amendment will become effective at 11:00 p.m., Eastern time, on December 31, 2002.

HOU03:884504.1

**RECEIVED**

**JAN 08 2003**

**DIV. OF OIL, GAS & MINING**

FROM RL&F#1

(THU) 12.12.02 13:32/ST. 13:31/NO. 4864756279 P 6

IN WITNESS WHEREOF, Phillips has caused this certificate to be executed this  
12th day of December, 2002.

PHILLIPS PETROLEUM COMPANY

W7

By: 

Name: Rick A. Harrington  
Title: Senior Vice President, Legal,  
and General Counsel

HOU03:884504.1

RECEIVED  
JAN 08 2003  
DIV. OF OIL, GAS & MINING

# Delaware

PAGE 1

*The First State*

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF MERGER, WHICH MERGES:

"CONOCO INC.", A DELAWARE CORPORATION,


WITH AND INTO "CONOCOPHILLIPS COMPANY" UNDER THE NAME OF "CONOCOPHILLIPS COMPANY", A CORPORATION ORGANIZED AND EXISTING UNDER THE LAWS OF THE STATE OF DELAWARE, AS RECEIVED AND FILED IN THIS OFFICE THE TWELFTH DAY OF DECEMBER, A.D. 2002, AT 1:44 O'CLOCK P.M.

AND I DO HEREBY FURTHER CERTIFY THAT THE EFFECTIVE DATE OF THE AFORESAID CERTIFICATE OF MERGER IS THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2002, AT 11:59 O'CLOCK P.M.

RECEIVED

JAN 08 2003

DIV. OF OIL, GAS & MINING



0064324 8100M

030002793

*Harriet Smith Windsor*  
Harriet Smith Windsor, Secretary of State

AUTHENTICATION: 2183370

DATE: 01-02-03



**CERTIFICATE OF MERGER**

of

**Conoco Inc.**  
 (a Delaware corporation)

with and into

**ConocoPhillips Company**  
 (a Delaware corporation)

Phillips Petroleum Company, a Delaware corporation to be renamed ConocoPhillips Company prior to the effective time of this certificate of merger (the "Surviving Corporation"), in compliance with the requirements of the General Corporation Law of the State of Delaware (the "DGCL") and desiring to effect a merger of Conoco Inc., a Delaware corporation formerly incorporated under the name Du Pont Holdings, Inc. (the "Merging Corporation" and together with the Surviving Corporation, the "Constituent Corporations"), with and into the Surviving Corporation, and acting by its duly authorized officer, DOES HEREBY CERTIFY that:

**First:** As of the date hereof, the name and state of incorporation of each of the Constituent Corporations of the merger are as follows:

| <u>NAME</u>                | <u>STATE OF INCORPORATION</u> |
|----------------------------|-------------------------------|
| PHILLIPS PETROLEUM COMPANY | Delaware                      |
| CONOCO INC.                | Delaware                      |

**Second:** An agreement and plan of merger has been approved, adopted, certified, executed and acknowledged by each of the Constituent Corporations in accordance with the requirements of Section 251 of the DGCL;

**Third:** The name of the Surviving Corporation will be ConocoPhillips Company;

**Fourth:** The Certificate of Incorporation of ConocoPhillips Company immediately prior to the merger shall be the Certificate of Incorporation of the Surviving Corporation until such time as it may be amended in accordance with applicable law and the provisions thereof;

**Fifth:** The executed agreement and plan of merger is on file at an office of the Surviving Corporation, the address of which is 600 North Dairy Ashford, Houston, Texas 77079;

RECEIVED

JAN 08 2003


DIV. OF OIL, GAS &amp; MINING

**Sixth:** A copy of the agreement and plan of merger will be furnished by the Surviving Corporation, on request and without cost, to any stockholder of any Constituent Corporation; and

**Seventh:** Pursuant to Section 103(d) of the DGCL, this certificate of merger will become effective at 11:59 p.m., Eastern time, on December 31, 2002.

Dated: December 12, 2002

**PHILLIPS PETROLEUM COMPANY**  
(a Delaware corporation)

By:   
Name: Rick A. Harrington  
Title: Senior Vice President, Legal,  
and General Counsel

STATE OF UTAH  
DEPARTMENT OF COMMERCE  
REGISTRATION

CONOCOPHILLIPS COMPANY

REFERENCE NUMBER(S), CLASSIFICATION(S) & DETAIL(S)

Corporation - Foreign - Profit  
562960-0143

EFFECTIVE  
06/14/1946

EXPIRATION  
\*RENEWAL

UNITED STATES CORP CO  
CONOCOPHILLIPS COMPANY  
GATEWAY TOWER EAST STE 900  
10 EAST SOUTH TEMPLE  
SLC UT 84133

RECEIVED

JAN 08 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF COMMERCE  
DIVISION OF CORPORATIONS & COMMERCIAL CODE  
REGISTRATION

EFFECTIVE DATE: 06/14/1946

EXPIRATION DATE: \*RENEWAL

ISSUED TO: CONOCOPHILLIPS COMPANY



REFERENCE NUMBER(S), CLASSIFICATION(S) & DETAIL(S)

562960-0143 Corporation - Foreign - Profit

\*RENEWAL

You will need to renew your registration each anniversary date of the effective date.

Exceptions: DBAs and Business Trusts renew every three (3) years from the effective date.

**Utah Well List as of 12/26/02**

| <b>API Well Number</b> | <b>Well Name</b>  | <b>Well Type</b> | <b>Well Status</b> | <b>Sec</b> | <b>Twpn</b> | <b>Twpd</b> | <b>Rngn</b> | <b>Rngd</b> |
|------------------------|-------------------|------------------|--------------------|------------|-------------|-------------|-------------|-------------|
| 43-007-30887-00-00     | ANDREEN 32-529    | Gas Well         | APD                | 32         | 14          | S           | 10          | E           |
| 43-007-30865-00-00     | COTNER 29-549     | Gas Well         | APD                | 29         | 14          | S           | 10          | E           |
| 43-007-30837-00-00     | DALLIN 32-615     | Gas Well         | APD                | 32         | 13          | S           | 9           | E           |
| 43-047-34551-00-00     | FED 43-24-3 #1    | Gas Well         | APD                | 24         | 10          | S           | 17          | E           |
| 43-047-33982-00-00     | FEDERAL 12-17 #1  | Gas Well         | APD                | 17         | 10          | S           | 18          | E           |
| 43-047-34471-00-00     | FEDERAL 12-29-7 1 | Gas Well         | APD                | 29         | 9           | S           | 19          | E           |
| 43-047-34472-00-00     | FEDERAL 31-31-6 1 | Gas Well         | APD                | 31         | 9           | S           | 19          | E           |
| 43-007-30864-00-00     | MCKENDRICK 29-548 | Gas Well         | APD                | 29         | 14          | S           | 10          | E           |
| 43-015-30512-00-00     | PPCO 19-379       | Gas Well         | APD                | 19         | 16          | S           | 9           | E           |
| 43-015-30515-00-00     | PPCO 24-562       | Gas Well         | APD                | 24         | 16          | S           | 8           | E           |
| 43-015-30548-00-00     | PPCO 30-605       | Gas Well         | APD                | 30         | 16          | S           | 9           | E           |
| 43-007-30888-00-00     | PRICE 32-438      | Gas Well         | APD                | 32         | 14          | S           | 10          | E           |
| 43-007-30813-00-00     | RITZAKIS 33-514   | Gas Well         | APD                | 33         | 13          | S           | 9           | E           |
| 43-007-30766-00-00     | RITZAKIS 33-516   | Gas Well         | APD                | 33         | 13          | S           | 9           | E           |
| 43-007-30838-00-00     | ROWLEY 32-616     | Gas Well         | APD                | 32         | 13          | S           | 9           | E           |
| 43-007-30863-00-00     | SCHMIDT 29-531    | Gas Well         | APD                | 29         | 14          | S           | 10          | E           |
| 43-007-30797-00-00     | SEELY 15-498      | Gas Well         | APD                | 15         | 14          | S           | 8           | E           |
| 43-007-30798-00-00     | SEELY 15-499      | Gas Well         | APD                | 15         | 14          | S           | 8           | E           |
| 43-007-30799-00-00     | SEELY 15-500      | Gas Well         | APD                | 15         | 14          | S           | 8           | E           |
| 43-007-30796-00-00     | SEELY 22-492      | Gas Well         | APD                | 22         | 14          | S           | 8           | E           |
| 43-007-30801-00-00     | SEELY 22-502      | Gas Well         | APD                | 22         | 14          | S           | 8           | E           |
| 43-007-30802-00-00     | SEELY 22-503      | Gas Well         | APD                | 22         | 14          | S           | 8           | E           |
| 43-007-30711-00-00     | USA 09-452        | Gas Well         | APD                | 9          | 15          | S           | 8           | E           |
| 43-015-30351-00-00     | USA 11-313        | Gas Well         | APD                | 11         | 16          | S           | 9           | E           |
| 43-015-30398-00-00     | USA 12-385        | Gas Well         | APD                | 12         | 16          | S           | 9           | E           |
| 43-015-30409-00-00     | USA 12-426        | Gas Well         | APD                | 12         | 16          | S           | 9           | E           |
| 43-007-30805-00-00     | USA 14-490        | Gas Well         | APD                | 14         | 14          | S           | 8           | E           |
| 43-007-30806-00-00     | USA 14-491        | Gas Well         | APD                | 14         | 14          | S           | 8           | E           |
| 43-007-30676-00-00     | USA 15-421        | Gas Well         | APD                | 15         | 15          | S           | 8           | E           |
| 43-015-30417-00-00     | USA 21-427        | Gas Well         | APD                | 21         | 16          | S           | 9           | E           |
| 43-015-30416-00-00     | USA 21-428        | Gas Well         | APD                | 21         | 16          | S           | 9           | E           |
| 43-015-30415-00-00     | USA 21-429        | Gas Well         | APD                | 21         | 16          | S           | 9           | E           |
| 43-007-30515-00-00     | USA 31-309        | Gas Well         | APD                | 31         | 15          | S           | 10          | E           |
| 43-007-30835-00-00     | USA 33-515        | Gas Well         | APD                | 33         | 13          | S           | 9           | E           |
| 43-007-30836-00-00     | USA 33-624        | Gas Well         | APD                | 33         | 13          | S           | 9           | E           |
| 43-007-30803-00-00     | USA 34-518        | Gas Well         | APD                | 34         | 14          | S           | 8           | E           |
| 43-007-30478-00-00     | UTAH 05-224       | Gas Well         | APD                | 5          | 15          | S           | 9           | E           |
| 43-015-30411-00-00     | UTAH 16-365       | Gas Well         | APD                | 16         | 16          | S           | 9           | E           |
| 43-015-30412-00-00     | UTAH 16-366       | Gas Well         | APD                | 16         | 16          | S           | 9           | E           |
| 43-015-30413-00-00     | UTAH 16-430       | Gas Well         | APD                | 16         | 16          | S           | 9           | E           |
| 43-015-30299-00-00     | UTAH 18-374       | Gas Well         | APD                | 18         | 16          | S           | 9           | E           |
| 43-015-30420-00-00     | UTAH 19-377       | Gas Well         | APD                | 19         | 16          | S           | 9           | E           |
| 43-015-30492-00-00     | UTAH 19-378       | Gas Well         | APD                | 19         | 16          | S           | 9           | E           |
| 43-007-30891-00-00     | UTAH 19-533       | Gas Well         | APD                | 19         | 14          | S           | 10          | E           |
| 43-015-30414-00-00     | UTAH 20-381       | Gas Well         | APD                | 20         | 16          | S           | 9           | E           |
| 43-015-30421-00-00     | UTAH 20-382       | Gas Well         | APD                | 20         | 16          | S           | 9           | E           |
| 43-015-30518-00-00     | UTAH 25-576       | Gas Well         | APD                | 25         | 16          | S           | 8           | E           |
| 43-015-30539-00-00     | UTAH 25-578       | Gas Well         | APD                | 25         | 16          | S           | 8           | E           |
| 43-015-30540-00-00     | UTAH 25-579       | Gas Well         | APD                | 25         | 16          | S           | 8           | E           |
| 43-007-30817-00-00     | UTAH 25-618       | Gas Well         | APD                | 25         | 13          | S           | 9           | E           |
| 43-015-30543-00-00     | UTAH 26-582       | Gas Well         | APD                | 26         | 16          | S           | 8           | E           |
| 43-015-30547-00-00     | UTAH 29-608       | Gas Well         | APD                | 29         | 16          | S           | 9           | E           |
| 43-007-30889-00-00     | UTAH 32-128       | Gas Well         | APD                | 32         | 14          | S           | 10          | E           |
| 43-007-30814-00-00     | UTAH 35-506       | Gas Well         | APD                | 35         | 13          | S           | 9           | E           |

**Utah Well List as of 12/26/02**

| <b>API Well Number</b> | <b>Well Name</b>         | <b>Well Type</b> | <b>Well Status</b> | <b>Sec</b> | <b>Twpn</b> | <b>Twps</b> | <b>Rngn</b> | <b>Rngd</b> |
|------------------------|--------------------------|------------------|--------------------|------------|-------------|-------------|-------------|-------------|
| 43-047-33750-00-00     | FEDERAL 34-29            | Gas Well         | P                  | 29         | 9           | S           | 19          | E           |
| 43-007-30782-00-00     | GAROFOLA 26-482          | Gas Well         | P                  | 26         | 15          | S           | 8           | E           |
| 43-007-30335-00-00     | GIACOLETTO 11-113        | Gas Well         | P                  | 11         | 14          | S           | 9           | E           |
| 43-007-30407-00-00     | GIACOLETTO 13-120        | Gas Well         | P                  | 13         | 14          | S           | 9           | E           |
| 43-007-30345-00-00     | GIACOLETTO 14-121        | Gas Well         | P                  | 14         | 14          | S           | 9           | E           |
| 43-007-30487-00-00     | HELPER & ASSOC 07-307    | Gas Well         | P                  | 7          | 15          | S           | 9           | E           |
| 43-007-30459-00-00     | HELPER & ASSOC 18-236    | Gas Well         | P                  | 18         | 15          | S           | 9           | E           |
| 43-007-30720-00-00     | HELPER & ASSOC 18-308    | Gas Well         | P                  | 18         | 15          | S           | 9           | E           |
| 43-007-30412-00-00     | HELPER & ASSOC 8-232     | Gas Well         | P                  | 8          | 15          | S           | 9           | E           |
| 43-007-30258-00-00     | HELPER & ASSOCIATES 7-84 | Gas Well         | P                  | 7          | 15          | S           | 9           | E           |
| 43-007-30588-00-00     | JENSEN 16-132            | Gas Well         | P                  | 16         | 15          | S           | 10          | E           |
| 43-007-30420-00-00     | KAKATSIDES 31-197        | Gas Well         | P                  | 31         | 14          | S           | 9           | E           |
| 43-007-30296-00-00     | LDS 17-133               | Gas Well         | P                  | 17         | 15          | S           | 10          | E           |
| 43-007-30323-00-00     | PAAR 16-146              | Gas Well         | P                  | 16         | 14          | S           | 9           | E           |
| 43-047-34286-00-00     | PETES WASH 23-12 #1      | Gas Well         | P                  | 12         | 10          | S           | 17          | E           |
| 43-007-30748-00-00     | PIERUCCI 25-461          | Gas Well         | P                  | 25         | 15          | S           | 8           | E           |
| 43-007-30749-00-00     | PIERUCCI 25-462          | Gas Well         | P                  | 25         | 15          | S           | 8           | E           |
| 43-007-30754-00-00     | PIERUCCI 26-463          | Gas Well         | P                  | 26         | 15          | S           | 8           | E           |
| 43-007-30755-00-00     | PIERUCCI 26-464          | Gas Well         | P                  | 26         | 15          | S           | 8           | E           |
| 43-007-30745-00-00     | PIERUCCI 26-481          | Gas Well         | P                  | 26         | 15          | S           | 8           | E           |
| 43-007-30117-00-00     | PINNACLE PEAK 19-171     | Gas Well         | P                  | 19         | 14          | S           | 9           | E           |
| 43-007-30845-00-00     | PMC 10-526               | Gas Well         | P                  | 10         | 15          | S           | 8           | E           |
| 43-007-30282-00-00     | POWELL 19-104            | Gas Well         | P                  | 19         | 15          | S           | 10          | E           |
| 43-007-30283-00-00     | POWELL 19-105            | Gas Well         | P                  | 19         | 15          | S           | 10          | E           |
| 43-007-30346-00-00     | POWELL 30-173            | Gas Well         | P                  | 30         | 15          | S           | 10          | E           |
| 43-015-30279-00-00     | PPCO 10-557              | Gas Well         | P                  | 10         | 16          | S           | 8           | E           |
| 43-015-30494-00-00     | PPCO 15-555              | Gas Well         | P                  | 15         | 16          | S           | 8           | E           |
| 43-007-30211-00-00     | PRETTYMAN 10-15-34       | Gas Well         | P                  | 10         | 14          | S           | 9           | E           |
| 43-007-30340-00-00     | PRETTYMAN 11-114         | Gas Well         | P                  | 11         | 14          | S           | 9           | E           |
| 43-007-30653-00-00     | RGC 21-331               | Gas Well         | P                  | 21         | 15          | S           | 9           | E           |
| 43-007-30743-00-00     | RGC 21-332               | Gas Well         | P                  | 21         | 15          | S           | 9           | E           |
| 43-007-30747-00-00     | RGC 25-460               | Gas Well         | P                  | 25         | 15          | S           | 8           | E           |
| 43-007-30559-00-00     | RGC 28-318               | Gas Well         | P                  | 28         | 15          | S           | 9           | E           |
| 43-007-30518-00-00     | RGC 28-319               | Gas Well         | P                  | 28         | 15          | S           | 9           | E           |
| 43-007-30509-00-00     | RITZAKIS 03-408          | Gas Well         | P                  | 3          | 14          | S           | 9           | E           |
| 43-007-30473-00-00     | RITZAKIS 5-304           | Gas Well         | P                  | 5          | 14          | S           | 9           | E           |
| 43-007-30474-00-00     | RITZAKIS 5-305           | Gas Well         | P                  | 5          | 14          | S           | 9           | E           |
| 43-007-30475-00-00     | RITZAKIS 8-298           | Gas Well         | P                  | 8          | 14          | S           | 9           | E           |
| 43-007-30479-00-00     | RITZAKIS 8-299           | Gas Well         | P                  | 8          | 14          | S           | 9           | E           |
| 43-007-30476-00-00     | RITZAKIS 8-300           | Gas Well         | P                  | 8          | 14          | S           | 9           | E           |
| 43-007-30374-00-00     | ROBERTSON 32-127         | Gas Well         | P                  | 32         | 14          | S           | 10          | E           |
| 43-007-30610-00-00     | SAMPINOS 16-131          | Gas Well         | P                  | 16         | 15          | S           | 10          | E           |
| 43-007-30723-00-00     | SAMPINOS 16-454          | Gas Well         | P                  | 16         | 15          | S           | 10          | E           |
| 43-007-30765-00-00     | SAMPINOS 16-521          | Gas Well         | P                  | 16         | 15          | S           | 10          | E           |
| 43-007-30800-00-00     | SEELY 22-501             | Gas Well         | P                  | 22         | 14          | S           | 8           | E           |
| 43-007-30130-00-00     | ST OF UT 25-9-1          | Gas Well         | P                  | 25         | 14          | S           | 9           | E           |
| 43-007-30142-00-00     | ST OF UT 36-3-4          | Gas Well         | P                  | 36         | 14          | S           | 9           | E           |
| 43-007-30116-00-00     | STELLA-HAMAKER 10-174    | Gas Well         | P                  | 10         | 15          | S           | 8           | E           |
| 43-007-30746-00-00     | TABOR 23-468             | Gas Well         | P                  | 23         | 15          | S           | 8           | E           |
| 43-007-30319-00-00     | TELONIS 15-142           | Gas Well         | P                  | 15         | 14          | S           | 9           | E           |
| 43-007-30322-00-00     | TELONIS 16-145           | Gas Well         | P                  | 16         | 14          | S           | 9           | E           |
| 43-007-30300-00-00     | TELONIS 19-150           | Gas Well         | P                  | 19         | 14          | S           | 9           | E           |
| 43-007-30299-00-00     | TELONIS 19-151           | Gas Well         | P                  | 19         | 14          | S           | 9           | E           |
| 43-007-30327-00-00     | TELONIS 20-152           | Gas Well         | P                  | 20         | 14          | S           | 9           | E           |

**Utah Well List as of 12/26/02**

| <b>API Well Number</b> | <b>Well Name</b> | <b>Well Type</b> | <b>Well Status</b> | <b>Sec</b> | <b>Twpn</b> | <b>Twpd</b> | <b>Rngn</b> | <b>Rngd</b> |
|------------------------|------------------|------------------|--------------------|------------|-------------|-------------|-------------|-------------|
| 43-007-30631-00-00     | USA 13-419       | Gas Well         | P                  | 13         | 15          | S           | 8           | E           |
| 43-007-30707-00-00     | USA 13-447       | Gas Well         | P                  | 13         | 14          | S           | 8           | E           |
| 43-007-30706-00-00     | USA 13-470       | Gas Well         | P                  | 13         | 14          | S           | 8           | E           |
| 43-007-30789-00-00     | USA 13-474       | Gas Well         | P                  | 13         | 14          | S           | 8           | E           |
| 43-007-30790-00-00     | USA 13-475       | Gas Well         | P                  | 13         | 14          | S           | 8           | E           |
| 43-007-30568-00-00     | USA 13-91        | Gas Well         | P                  | 13         | 14          | S           | 9           | E           |
| 43-007-30404-00-00     | USA 14-122       | Gas Well         | P                  | 14         | 14          | S           | 9           | E           |
| 43-015-30418-00-00     | USA 1-425        | Gas Well         | P                  | 1          | 16          | S           | 9           | E           |
| 43-007-30579-00-00     | USA 14-325       | Gas Well         | P                  | 14         | 15          | S           | 8           | E           |
| 43-007-30634-00-00     | USA 14-386       | Gas Well         | P                  | 14         | 15          | S           | 8           | E           |
| 43-007-30646-00-00     | USA 14-416       | Gas Well         | P                  | 14         | 15          | S           | 8           | E           |
| 43-007-30647-00-00     | USA 14-417       | Gas Well         | P                  | 14         | 15          | S           | 8           | E           |
| 43-007-30791-00-00     | USA 14-476       | Gas Well         | P                  | 14         | 14          | S           | 8           | E           |
| 43-007-30792-00-00     | USA 14-477       | Gas Well         | P                  | 14         | 14          | S           | 8           | E           |
| 43-007-30529-00-00     | USA 14-74        | Gas Well         | P                  | 14         | 14          | S           | 9           | E           |
| 43-007-30263-00-00     | USA 14-75        | Gas Well         | P                  | 14         | 14          | S           | 9           | E           |
| 43-007-30450-00-00     | USA 15-176       | Gas Well         | P                  | 15         | 14          | S           | 9           | E           |
| 43-007-30423-00-00     | USA 15-177       | Gas Well         | P                  | 15         | 14          | S           | 9           | E           |
| 43-007-30690-00-00     | USA 15-420       | Gas Well         | P                  | 15         | 15          | S           | 8           | E           |
| 43-007-30691-00-00     | USA 15-422       | Gas Well         | P                  | 15         | 15          | S           | 8           | E           |
| 43-007-30264-00-00     | USA 15-88        | Gas Well         | P                  | 15         | 14          | S           | 9           | E           |
| 43-007-30422-00-00     | USA 17-179       | Gas Well         | P                  | 17         | 14          | S           | 9           | E           |
| 43-007-30622-00-00     | USA 17-180A      | Gas Well         | P                  | 17         | 14          | S           | 9           | E           |
| 43-007-30618-00-00     | USA 18-181       | Gas Well         | P                  | 18         | 14          | S           | 9           | E           |
| 43-007-30417-00-00     | USA 18-182       | Gas Well         | P                  | 18         | 14          | S           | 9           | E           |
| 43-007-30619-00-00     | USA 18-435       | Gas Well         | P                  | 18         | 14          | S           | 9           | E           |
| 43-007-30393-00-00     | USA 19-222       | Gas Well         | P                  | 19         | 15          | S           | 10          | E           |
| 43-007-30392-00-00     | USA 19-73        | Gas Well         | P                  | 19         | 15          | S           | 10          | E           |
| 43-007-30448-00-00     | USA 20-287       | Gas Well         | P                  | 20         | 15          | S           | 10          | E           |
| 43-007-30451-00-00     | USA 20-288       | Gas Well         | P                  | 20         | 15          | S           | 10          | E           |
| 43-007-30590-00-00     | USA 20-398       | Gas Well         | P                  | 20         | 15          | S           | 10          | E           |
| 43-007-30591-00-00     | USA 20-399       | Gas Well         | P                  | 20         | 15          | S           | 10          | E           |
| 43-007-30424-00-00     | USA 21-184       | Gas Well         | P                  | 21         | 14          | S           | 9           | E           |
| 43-007-30425-00-00     | USA 21-35        | Gas Well         | P                  | 21         | 14          | S           | 9           | E           |
| 43-007-30426-00-00     | USA 22-185       | Gas Well         | P                  | 22         | 14          | S           | 9           | E           |
| 43-007-30477-00-00     | USA 22-186       | Gas Well         | P                  | 22         | 14          | S           | 9           | E           |
| 43-007-30700-00-00     | USA 22-466       | Gas Well         | P                  | 22         | 15          | S           | 8           | E           |
| 43-007-30611-00-00     | USA 23-423       | Gas Well         | P                  | 23         | 14          | S           | 8           | E           |
| 43-007-30650-00-00     | USA 23-445       | Gas Well         | P                  | 23         | 15          | S           | 8           | E           |
| 43-007-30704-00-00     | USA 23-451       | Gas Well         | P                  | 23         | 15          | S           | 8           | E           |
| 43-007-30503-00-00     | USA 23-467       | Gas Well         | P                  | 23         | 15          | S           | 8           | E           |
| 43-007-30793-00-00     | USA 23-478       | Gas Well         | P                  | 23         | 14          | S           | 8           | E           |
| 43-007-30794-00-00     | USA 23-479       | Gas Well         | P                  | 23         | 14          | S           | 8           | E           |
| 43-007-30795-00-00     | USA 23-480       | Gas Well         | P                  | 23         | 14          | S           | 8           | E           |
| 43-007-30469-00-00     | USA 24-183       | Gas Well         | P                  | 24         | 14          | S           | 8           | E           |
| 43-007-30612-00-00     | USA 24-387       | Gas Well         | P                  | 24         | 14          | S           | 8           | E           |
| 43-007-30613-00-00     | USA 24-388       | Gas Well         | P                  | 24         | 14          | S           | 8           | E           |
| 43-007-30651-00-00     | USA 24-443       | Gas Well         | P                  | 24         | 15          | S           | 8           | E           |
| 43-007-30648-00-00     | USA 24-444       | Gas Well         | P                  | 24         | 15          | S           | 8           | E           |
| 43-007-30708-00-00     | USA 24-446       | Gas Well         | P                  | 24         | 14          | S           | 8           | E           |
| 43-007-30652-00-00     | USA 24-448       | Gas Well         | P                  | 24         | 15          | S           | 8           | E           |
| 43-007-30705-00-00     | USA 24-449       | Gas Well         | P                  | 24         | 15          | S           | 8           | E           |
| 43-007-30505-00-00     | USA 25-459       | Gas Well         | P                  | 25         | 15          | S           | 8           | E           |
| 43-007-30614-00-00     | USA 26-393       | Gas Well         | P                  | 26         | 14          | S           | 8           | E           |

**Utah Well List as of 12/26/02**

| <b>API Well Number</b> | <b>Well Name</b> | <b>Well Type</b> | <b>Well Status</b> | <b>Sec</b> | <b>Twpn</b> | <b>Twpd</b> | <b>Rngn</b> | <b>Rngd</b> |
|------------------------|------------------|------------------|--------------------|------------|-------------|-------------|-------------|-------------|
| 43-007-30430-00-00     | UTAH 06-223      | Gas Well         | P                  | 6          | 15          | S           | 9           | E           |
| 43-007-30562-00-00     | UTAH 06-330      | Gas Well         | P                  | 6          | 15          | S           | 9           | E           |
| 43-007-30716-00-00     | UTAH 06-483      | Gas Well         | P                  | 6          | 15          | S           | 9           | E           |
| 43-007-30409-00-00     | UTAH 07-234      | Gas Well         | P                  | 7          | 15          | S           | 9           | E           |
| 43-007-30421-00-00     | UTAH 07-235      | Gas Well         | P                  | 7          | 15          | S           | 9           | E           |
| 43-007-30411-00-00     | UTAH 08-231      | Gas Well         | P                  | 8          | 15          | S           | 9           | E           |
| 43-007-30488-00-00     | UTAH 08-233      | Gas Well         | P                  | 8          | 15          | S           | 9           | E           |
| 43-015-30464-00-00     | UTAH 08-354      | Gas Well         | P                  | 8          | 16          | S           | 9           | E           |
| 43-015-30378-00-00     | UTAH 08-355      | Gas Well         | P                  | 8          | 16          | S           | 9           | E           |
| 43-015-30379-00-00     | UTAH 08-356      | Gas Well         | P                  | 8          | 16          | S           | 9           | E           |
| 43-015-30380-00-00     | UTAH 08-357      | Gas Well         | P                  | 8          | 16          | S           | 9           | E           |
| 43-007-30449-00-00     | UTAH 09-227      | Gas Well         | P                  | 9          | 15          | S           | 9           | E           |
| 43-007-30561-00-00     | UTAH 09-329      | Gas Well         | P                  | 9          | 15          | S           | 9           | E           |
| 43-015-30300-00-00     | UTAH 09-358      | Gas Well         | P                  | 9          | 16          | S           | 9           | E           |
| 43-015-30407-00-00     | UTAH 09-359      | Gas Well         | P                  | 9          | 16          | S           | 9           | E           |
| 43-015-30397-00-00     | UTAH 09-360      | Gas Well         | P                  | 9          | 16          | S           | 9           | E           |
| 43-015-30408-00-00     | UTAH 09-361      | Gas Well         | P                  | 9          | 16          | S           | 9           | E           |
| 43-007-30580-00-00     | UTAH 09-412      | Gas Well         | P                  | 9          | 15          | S           | 10          | E           |
| 43-007-30605-00-00     | UTAH 09-413      | Gas Well         | P                  | 9          | 15          | S           | 10          | E           |
| 43-007-30657-00-00     | UTAH 09-450      | Gas Well         | P                  | 9          | 15          | S           | 10          | E           |
| 43-007-30722-00-00     | UTAH 09-453      | Gas Well         | P                  | 9          | 15          | S           | 10          | E           |
| 43-007-30302-00-00     | UTAH 10-01-36    | Gas Well         | P                  | 10         | 15          | S           | 9           | E           |
| 43-007-30298-00-00     | UTAH 10-219      | Gas Well         | P                  | 10         | 15          | S           | 9           | E           |
| 43-007-30432-00-00     | UTAH 10-220      | Gas Well         | P                  | 10         | 15          | S           | 9           | E           |
| 43-007-30303-00-00     | UTAH 10-221      | Gas Well         | P                  | 10         | 15          | S           | 9           | E           |
| 43-007-30228-00-00     | UTAH 11-50       | Gas Well         | P                  | 11         | 15          | S           | 9           | E           |
| 43-007-30229-00-00     | UTAH 11-51       | Gas Well         | P                  | 11         | 15          | S           | 9           | E           |
| 43-007-30230-00-00     | UTAH 11-52       | Gas Well         | P                  | 11         | 15          | S           | 9           | E           |
| 43-007-30231-00-00     | UTAH 11-53       | Gas Well         | P                  | 11         | 15          | S           | 9           | E           |
| 43-007-30467-00-00     | UTAH 1-209       | Gas Well         | P                  | 1          | 15          | S           | 8           | E           |
| 43-007-30210-00-00     | UTAH 12-15-37    | Gas Well         | P                  | 12         | 15          | S           | 9           | E           |
| 43-007-30232-00-00     | UTAH 12-54       | Gas Well         | P                  | 12         | 15          | S           | 9           | E           |
| 43-007-30233-00-00     | UTAH 12-55       | Gas Well         | P                  | 12         | 15          | S           | 9           | E           |
| 43-007-30234-00-00     | UTAH 12-56       | Gas Well         | P                  | 12         | 15          | S           | 9           | E           |
| 43-015-30493-00-00     | UTAH 13-376      | Gas Well         | P                  | 13         | 16          | S           | 8           | E           |
| 43-015-30301-00-00     | UTAH 13-550      | Gas Well         | P                  | 13         | 16          | S           | 8           | E           |
| 43-007-30243-00-00     | UTAH 13-65       | Gas Well         | P                  | 13         | 15          | S           | 9           | E           |
| 43-007-30244-00-00     | UTAH 13-66       | Gas Well         | P                  | 13         | 15          | S           | 9           | E           |
| 43-007-30245-00-00     | UTAH 13-67       | Gas Well         | P                  | 13         | 15          | S           | 9           | E           |
| 43-007-30246-00-00     | UTAH 13-68       | Gas Well         | P                  | 13         | 15          | S           | 9           | E           |
| 43-007-30439-00-00     | UTAH 13-92       | Gas Well         | P                  | 13         | 14          | S           | 9           | E           |
| 43-007-30220-00-00     | UTAH 1-42        | Gas Well         | P                  | 1          | 15          | S           | 9           | E           |
| 43-007-30221-00-00     | UTAH 1-43        | Gas Well         | P                  | 1          | 15          | S           | 9           | E           |
| 43-007-30222-00-00     | UTAH 1-44        | Gas Well         | P                  | 1          | 15          | S           | 9           | E           |
| 43-007-30223-00-00     | UTAH 1-45        | Gas Well         | P                  | 1          | 15          | S           | 9           | E           |
| 43-015-30330-00-00     | UTAH 14-551      | Gas Well         | P                  | 14         | 16          | S           | 8           | E           |
| 43-015-30331-00-00     | UTAH 14-552      | Gas Well         | P                  | 14         | 16          | S           | 8           | E           |
| 43-007-30239-00-00     | UTAH 14-61       | Gas Well         | P                  | 14         | 15          | S           | 9           | E           |
| 43-007-30240-00-00     | UTAH 14-62       | Gas Well         | P                  | 14         | 15          | S           | 9           | E           |
| 43-007-30241-00-00     | UTAH 14-63       | Gas Well         | P                  | 14         | 15          | S           | 9           | E           |
| 43-007-30242-00-00     | UTAH 14-64       | Gas Well         | P                  | 14         | 15          | S           | 9           | E           |
| 43-015-30334-00-00     | UTAH 15-553      | Gas Well         | P                  | 15         | 16          | S           | 8           | E           |
| 43-007-30416-00-00     | UTAH 17-101      | Gas Well         | P                  | 17         | 15          | S           | 10          | E           |
| 43-007-30277-00-00     | UTAH 17-102      | Gas Well         | P                  | 17         | 15          | S           | 10          | E           |

**Utah Well List as of 12/26/02**

| <b>API Well Number</b> | <b>Well Name</b> | <b>Well Type</b> | <b>Well Status</b> | <b>Sec</b> | <b>Twpn</b> | <b>Twpd</b> | <b>Rngn</b> | <b>Rngd</b> |
|------------------------|------------------|------------------|--------------------|------------|-------------|-------------|-------------|-------------|
| 43-007-30255-00-00     | UTAH 24-80       | Gas Well         | P                  | 24         | 15          | S           | 9           | E           |
| 43-007-30256-00-00     | UTAH 24-81       | Gas Well         | P                  | 24         | 15          | S           | 9           | E           |
| 43-007-30267-00-00     | UTAH 24-86       | Gas Well         | P                  | 24         | 15          | S           | 9           | E           |
| 43-007-30375-00-00     | UTAH 24-87       | Gas Well         | P                  | 24         | 15          | S           | 9           | E           |
| 43-007-30227-00-00     | UTAH 2-49        | Gas Well         | P                  | 2          | 15          | S           | 9           | E           |
| 43-007-30157-00-00     | UTAH 25-11-7     | Gas Well         | P                  | 25         | 14          | S           | 9           | E           |
| 43-007-30399-00-00     | UTAH 25-134      | Gas Well         | P                  | 25         | 15          | S           | 9           | E           |
| 43-007-30400-00-00     | UTAH 25-252      | Gas Well         | P                  | 25         | 15          | S           | 9           | E           |
| 43-007-30401-00-00     | UTAH 25-253      | Gas Well         | P                  | 25         | 15          | S           | 9           | E           |
| 43-007-30402-00-00     | UTAH 25-254      | Gas Well         | P                  | 25         | 15          | S           | 9           | E           |
| 43-007-30600-00-00     | UTAH 25-389      | Gas Well         | P                  | 25         | 14          | S           | 8           | E           |
| 43-007-30599-00-00     | UTAH 25-390      | Gas Well         | P                  | 25         | 14          | S           | 8           | E           |
| 43-007-30658-00-00     | UTAH 25-391      | Gas Well         | P                  | 25         | 14          | S           | 8           | E           |
| 43-007-30602-00-00     | UTAH 25-392      | Gas Well         | P                  | 25         | 14          | S           | 8           | E           |
| 43-007-30206-00-00     | UTAH 25-4-33     | Gas Well         | P                  | 25         | 14          | S           | 9           | E           |
| 43-015-30519-00-00     | UTAH 25-577      | Gas Well         | P                  | 25         | 16          | S           | 8           | E           |
| 43-007-30156-00-00     | UTAH 25-7-6      | Gas Well         | P                  | 25         | 14          | S           | 9           | E           |
| 43-007-30204-00-00     | UTAH 26-11-25    | Gas Well         | P                  | 26         | 14          | S           | 9           | E           |
| 43-007-30205-00-00     | UTAH 26-1-23     | Gas Well         | P                  | 26         | 14          | S           | 9           | E           |
| 43-007-30181-00-00     | UTAH 26-16-8     | Gas Well         | P                  | 26         | 14          | S           | 9           | E           |
| 43-007-30446-00-00     | UTAH 26-255      | Gas Well         | P                  | 26         | 15          | S           | 9           | E           |
| 43-007-30445-00-00     | UTAH 26-256      | Gas Well         | P                  | 26         | 15          | S           | 9           | E           |
| 43-007-30444-00-00     | UTAH 26-257      | Gas Well         | P                  | 26         | 15          | S           | 9           | E           |
| 43-007-30514-00-00     | UTAH 26-267      | Gas Well         | P                  | 26         | 15          | S           | 9           | E           |
| 43-015-30541-00-00     | UTAH 26-580      | Gas Well         | P                  | 26         | 16          | S           | 8           | E           |
| 43-015-30542-00-00     | UTAH 26-581      | Gas Well         | P                  | 26         | 16          | S           | 8           | E           |
| 43-015-30544-00-00     | UTAH 26-583      | Gas Well         | P                  | 26         | 16          | S           | 8           | E           |
| 43-007-30202-00-00     | UTAH 26-6-24     | Gas Well         | P                  | 26         | 14          | S           | 9           | E           |
| 43-007-30395-00-00     | UTAH 27-187      | Gas Well         | P                  | 27         | 14          | S           | 9           | E           |
| 43-007-30292-00-00     | UTAH 27-188      | Gas Well         | P                  | 27         | 14          | S           | 9           | E           |
| 43-007-30457-00-00     | UTAH 27-268      | Gas Well         | P                  | 27         | 15          | S           | 9           | E           |
| 43-007-30458-00-00     | UTAH 27-269      | Gas Well         | P                  | 27         | 15          | S           | 9           | E           |
| 43-007-30712-00-00     | UTAH 27-457      | Gas Well         | P                  | 27         | 14          | S           | 8           | E           |
| 43-007-30714-00-00     | UTAH 27-458      | Gas Well         | P                  | 27         | 14          | S           | 8           | E           |
| 43-007-30777-00-00     | UTAH 27-520      | Gas Well         | P                  | 27         | 14          | S           | 8           | E           |
| 43-015-30545-00-00     | UTAH 27-584      | Gas Well         | P                  | 27         | 16          | S           | 8           | E           |
| 43-007-30193-00-00     | UTAH 27-8-29     | Gas Well         | P                  | 27         | 14          | S           | 9           | E           |
| 43-007-30186-00-00     | UTAH 27-9-30     | Gas Well         | P                  | 27         | 14          | S           | 9           | E           |
| 43-007-30396-00-00     | UTAH 28-189      | Gas Well         | P                  | 28         | 14          | S           | 9           | E           |
| 43-007-30397-00-00     | UTAH 28-190      | Gas Well         | P                  | 28         | 14          | S           | 9           | E           |
| 43-007-30293-00-00     | UTAH 28-191      | Gas Well         | P                  | 28         | 14          | S           | 9           | E           |
| 43-007-30294-00-00     | UTAH 28-192      | Gas Well         | P                  | 28         | 14          | S           | 9           | E           |
| 43-007-30551-00-00     | UTAH 28-320      | Gas Well         | P                  | 28         | 15          | S           | 9           | E           |
| 43-007-30560-00-00     | UTAH 28-321      | Gas Well         | P                  | 28         | 15          | S           | 9           | E           |
| 43-007-30405-00-00     | UTAH 29-193      | Gas Well         | P                  | 29         | 14          | S           | 9           | E           |
| 43-007-30427-00-00     | UTAH 29-194      | Gas Well         | P                  | 29         | 14          | S           | 9           | E           |
| 43-007-30739-00-00     | UTAH 29-339      | Gas Well         | P                  | 29         | 15          | S           | 9           | E           |
| 43-007-30740-00-00     | UTAH 29-340      | Gas Well         | P                  | 29         | 15          | S           | 9           | E           |
| 43-007-30741-00-00     | UTAH 29-341      | Gas Well         | P                  | 29         | 15          | S           | 9           | E           |
| 43-007-30742-00-00     | UTAH 29-342      | Gas Well         | P                  | 29         | 15          | S           | 9           | E           |
| 43-007-30262-00-00     | UTAH 30-125      | Gas Well         | P                  | 30         | 14          | S           | 10          | E           |
| 43-007-30185-00-00     | UTAH 30-13-14    | Gas Well         | P                  | 30         | 14          | S           | 10          | E           |
| 43-007-30265-00-00     | UTAH 30-195      | Gas Well         | P                  | 30         | 14          | S           | 9           | E           |
| 43-007-30344-00-00     | UTAH 30-196      | Gas Well         | P                  | 30         | 14          | S           | 9           | E           |



**Utah Well List as of 12/26/02**

| <b>API Well Number</b> | <b>Well Name</b>     | <b>Well Type</b> | <b>Well Status</b> | <b>Sec</b> | <b>Twpn</b> | <b>Twpd</b> | <b>Rngn</b> | <b>Rngd</b> |
|------------------------|----------------------|------------------|--------------------|------------|-------------|-------------|-------------|-------------|
| 43-007-30178-00-00     | UTAH 36-1-2          | Gas Well         | P                  | 36         | 14          | S           | 9           | E           |
| 43-007-30341-00-00     | UTAH 36-135          | Gas Well         | P                  | 36         | 15          | S           | 9           | E           |
| 43-007-30343-00-00     | UTAH 36-136          | Gas Well         | P                  | 36         | 15          | S           | 9           | E           |
| 43-007-30342-00-00     | UTAH 36-137          | Gas Well         | P                  | 36         | 15          | S           | 9           | E           |
| 43-007-30315-00-00     | UTAH 36-162          | Gas Well         | P                  | 36         | 14          | S           | 8           | E           |
| 43-007-30316-00-00     | UTAH 36-163          | Gas Well         | P                  | 36         | 14          | S           | 8           | E           |
| 43-007-30317-00-00     | UTAH 36-164          | Gas Well         | P                  | 36         | 14          | S           | 8           | E           |
| 43-007-30318-00-00     | UTAH 36-165          | Gas Well         | P                  | 36         | 14          | S           | 8           | E           |
| 43-007-30144-00-00     | UTAH 36-9-5          | Gas Well         | P                  | 36         | 14          | S           | 9           | E           |
| 43-015-30341-00-00     | UTAH 4-280           | Gas Well         | P                  | 4          | 16          | S           | 9           | E           |
| 43-015-30342-00-00     | UTAH 4-282           | Gas Well         | P                  | 4          | 16          | S           | 9           | E           |
| 43-007-30384-00-00     | UTAH 5-205           | Gas Well         | P                  | 5          | 15          | S           | 9           | E           |
| 43-007-30269-00-00     | UTAH 5-94            | Gas Well         | P                  | 5          | 15          | S           | 10          | E           |
| 43-007-30270-00-00     | UTAH 5-95            | Gas Well         | P                  | 5          | 15          | S           | 10          | E           |
| 43-007-30271-00-00     | UTAH 5-96            | Gas Well         | P                  | 5          | 15          | S           | 10          | E           |
| 43-007-30217-00-00     | UTAH 6-38            | Gas Well         | P                  | 6          | 15          | S           | 10          | E           |
| 43-007-30218-00-00     | UTAH 6-39            | Gas Well         | P                  | 6          | 15          | S           | 10          | E           |
| 43-007-30219-00-00     | UTAH 6-40            | Gas Well         | P                  | 6          | 15          | S           | 10          | E           |
| 43-007-30254-00-00     | UTAH 6-41            | Gas Well         | P                  | 6          | 15          | S           | 10          | E           |
| 43-007-30235-00-00     | UTAH 7-57            | Gas Well         | P                  | 7          | 15          | S           | 10          | E           |
| 43-007-30236-00-00     | UTAH 7-58            | Gas Well         | P                  | 7          | 15          | S           | 10          | E           |
| 43-007-30237-00-00     | UTAH 7-59            | Gas Well         | P                  | 7          | 15          | S           | 10          | E           |
| 43-007-30238-00-00     | UTAH 7-60            | Gas Well         | P                  | 7          | 15          | S           | 10          | E           |
| 43-007-30275-00-00     | UTAH 8-100           | Gas Well         | P                  | 8          | 15          | S           | 10          | E           |
| 43-007-30410-00-00     | UTAH 8-230           | Gas Well         | P                  | 8          | 15          | S           | 9           | E           |
| 43-007-30272-00-00     | UTAH 8-97            | Gas Well         | P                  | 8          | 15          | S           | 10          | E           |
| 43-007-30285-00-00     | UTAH 8-98X           | Gas Well         | P                  | 8          | 15          | S           | 10          | E           |
| 43-007-30274-00-00     | UTAH 8-99            | Gas Well         | P                  | 8          | 15          | S           | 10          | E           |
| 43-007-30413-00-00     | UTAH 9-228           | Gas Well         | P                  | 9          | 15          | S           | 9           | E           |
| 43-007-30414-00-00     | UTAH 9-229           | Gas Well         | P                  | 9          | 15          | S           | 9           | E           |
| 43-007-30279-00-00     | WILLIAMS 30-78       | Gas Well         | P                  | 30         | 14          | S           | 10          | E           |
| 43-007-30481-00-00     | WOOLSTENHULME 05-266 | Gas Well         | P                  | 5          | 15          | S           | 10          | E           |
| 43-015-30250-00-00     | UTAH 16-110          | Gas Well         | Shut In            | 16         | 16          | S           | 9           | E           |



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Eastern States Office  
7450 Boston Boulevard  
Springfield, Virginia 22153

IN REPLY REFER TO  
3106.8(932.34)WF

January 16, 2003

### NOTICE

|                              |   |                  |
|------------------------------|---|------------------|
| ConocoPhillips Company       | : | Oil & Gas Leases |
| P.O. Box 7500                | : |                  |
| Bartlesville, Oklahoma 74005 | : |                  |

### Merger/Name Change Recognized

Acceptable evidence was received in this office on January 14, 2003, concerning the change of name of Phillips Petroleum Company to **ConocoPhillips Company** and the merger of **Conoco Incorporated** into **ConocoPhillips Company** on Federal oil and gas leases, with **ConocoPhillips Company** being the surviving entity.

The Secretary of the State of Delaware certified the effective date of this merger effective December 31, 2002.

The oil and gas lease files identified on the enclosed exhibit have been noted to the merger. The exhibit was compiled from a list of leases obtained from your list of leases. Eastern States has not abstracted the lease files to determine if the entities affected by this merger hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested record title or operating rights interest. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of this merger and name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify other leases in which the merging entity maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

By Operation of law the name of the principal on Nationwide Oil and Gas Bond held by Conoco Incorporated (ES0085) has been changed to ConocoPhillips Company.

If you have any questions, please contact Bill Forbes at 703-440-1536.

*S/ Wilbert B. Forbes*

Wilbert B. Forbes  
Land Law Examiner  
Branch of Use Authorization  
Division of Resources Planning, Use  
and Protection

bc: JFO, BLM State Offices, MMS, ES RF, 930 RF, ES-932:  
Bforbes:wbf:01/16/03:440-1536/ConocoPhillips Co

## OPERATOR CHANGE WORKSHEET

## ROUTING

|         |
|---------|
| 1. GLH  |
| 2. CDW✓ |
| 3. FILE |

Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

**X Merger**The operator of the well(s) listed below has changed, effective: **12-31-02**

|                              |                                 |
|------------------------------|---------------------------------|
| <b>FROM: (Old Operator):</b> | <b>TO: ( New Operator):</b>     |
| PHILLIPS PETROLEUM COMPANY   | CONOCOPHILLIPS COMPANY          |
| Address: 980 PLAZA OFFICE    | Address: P O BOX 2197, WL3 4066 |
|                              |                                 |
| BARTLESVILLE, OK 74004       | HOUSTON, TX 77252               |
| Phone: 1-(918)-661-4415      | Phone: 1-(832)-486-2329         |
| Account No. N1475            | Account No. N2335               |

CA No.

Unit:

## WELL(S)

| NAME                      | SEC TWN<br>RNG | API NO       | ENTITY<br>NO | LEASE<br>TYPE | WELL<br>TYPE | WELL<br>STATUS |
|---------------------------|----------------|--------------|--------------|---------------|--------------|----------------|
| RGC 28-319                | 28-15S-09E     | 43-007-30518 | 13111        | FEE           | GW           | P              |
| UTAH 29-339               | 29-15S-09E     | 43-007-30739 | 13151        | STATE         | GW           | P              |
| UTAH 29-340               | 29-15S-09E     | 43-007-30740 | 13152        | STATE         | GW           | P              |
| UTAH 29-341               | 29-15S-09E     | 43-007-30741 | 13254        | STATE         | GW           | P              |
| UTAH 29-342               | 29-15S-09E     | 43-007-30742 | 13262        | STATE         | GW           | P              |
| UTAH 30-484               | 30-15S-09E     | 43-007-30750 | 13153        | STATE         | GW           | P              |
| UTAH 30-485               | 30-15S-09E     | 43-007-30751 | 13154        | STATE         | GW           | P              |
| UTAH 30-486               | 30-15S-09E     | 43-007-30752 | 13256        | STATE         | GW           | P              |
| UTAH 30-487               | 30-15S-09E     | 43-007-30753 | 13255        | STATE         | GW           | P              |
| UTAH 34-688               | 34-15S-09E     | 43-007-30847 | 99999        | STATE         | GW           | NEW            |
| UTAH 27-686               | 27-16S-09E     | 43-007-30848 | 99999        | STATE         | GW           | NEW            |
| PEIRCE 04-494             | 04-15S-10E     | 43-007-30856 | 13687        | FEE           | GW           | DRL            |
| PEIRCE 04-440             | 04-15S-10E     | 43-007-30857 | 13688        | FEE           | GW           | DRL            |
| BORRELL 10-695            | 10-15S-10E     | 43-007-30861 | 13686        | FEE           | GW           | DRL            |
| USA 10-696                | 10-15S-10E     | 43-007-30862 | 99999        | FEDERAL       | GW           | NEW            |
| UTAH 21-83                | 21-15S-10E     | 43-007-30259 | 11712        | STATE         | GW           | P              |
| USA 29-455 (CA UTU-79452) | 29-15S-10E     | 43-007-30507 | 13110        | FEDERAL       | GW           | P              |
| USA 31-309                | 31-15S-10E     | 43-007-30515 | 99999        | FEDERAL       | GW           | APD            |
| UTAH 10-556               | 10-16S-08E     | 43-015-30266 | 99999        | STATE         | GW           | NEW            |
| PPCO 10-557               | 10-16S-08E     | 43-015-30279 | 13633        | FEE           | GW           | P              |

## OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 01/08/2003
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 01/08/2003
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 02/03/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 562960-0143
5. If **NO**, the operator was contacted on: \_\_\_\_\_

6. (R649-9-2)Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: 01/14/2003

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 01/14/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: 01/14/2003

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

**DATA ENTRY:**

1. Changes entered in the **Oil and Gas Database** on: 02/13/2003

2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 02/13/2003

3. Bond information entered in RBDMS on: N/A

4. Fee wells attached to bond in RBDMS on: N/A

**STATE WELL(S) BOND VERIFICATION:**

1. State well(s) covered by Bond Number: 8140-60-24

**FEDERAL WELL(S) BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: 8015-16-69

**INDIAN WELL(S) BOND VERIFICATION:**

1. Indian well(s) covered by Bond Number: N/A

**FEE WELL(S) BOND VERIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 6196922

2. The **FORMER** operator has requested a release of liability from their bond on: N/A  
The Division sent response by letter on: N/A

**LEASE INTEREST OWNER NOTIFICATION:**

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

**COMMENTS:**

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

# ORIGINAL

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☐ GAS ☐ OTHER ☒

2. Name of Operator:

ConocoPhillips Company

3. Address and Telephone Number:

6825 South 5300 West, P.O. Box 851, Price, UT 84501 (435) 613-9777

4. Location of Well  
Footages:

940' FNL, 789' FWL

QQ, Sec., T., R., M.:

NW/SW, SEC. 29, T15S, R10E, SLB & M

5. Lease Designation and Serial Number:

UTU-73075

6. If Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

UTU67921X Drunkards Wash

8. Well Name and Number:

USA 29-455

9. API Well Number:

43-007-30507

10. Field or Pool, or Wildcat:

Drunkards Wash

County: Carbon County

State: Utah

### 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

#### NOTICE OF INTENT (Submit in Duplicate)

- |  |  |
|--|--|
| <input type="checkbox"/> Abandon                   | <input type="checkbox"/> New Construction  |
| <input type="checkbox"/> Repair Casing             | <input type="checkbox"/> Pull or Alter Csg |
| <input type="checkbox"/> Change of Plans           | <input type="checkbox"/> Recomplete        |
| <input type="checkbox"/> Convert to Injection      | <input type="checkbox"/> Reperforate       |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare     |
| <input type="checkbox"/> Multiple Completion       | <input type="checkbox"/> Water Shut-Off    |
| <input type="checkbox"/> Other _____               |  |
- Approximate date work will start \_\_\_\_\_

#### SUBSEQUENT REPORT (Submit Original Form Only)

- |   |  |
|---|--|
| <input type="checkbox"/> Abandon *  | <input type="checkbox"/> New Construction  |
| <input type="checkbox"/> Repair Casing                                    | <input type="checkbox"/> Pull or Alter Csg |
| <input type="checkbox"/> Change of Plans                                  | <input type="checkbox"/> Reperforate       |
| <input type="checkbox"/> Convert to Injection                             | <input type="checkbox"/> Vent or Flare     |
| <input type="checkbox"/> Fracture Treat or Acidize                        | <input type="checkbox"/> Water Shut-Off    |
| <input checked="" type="checkbox"/> Other <u>Chemical/Flush Treatment</u> |  |
- Date of work completion 07/22/2005

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

\* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please be advised that the above referenced well was chemically treated with 250 gallons of 15% HCL & 185 gallons low Ph fluid on 07/22/2005.

13.

Name & Signature: Lynnette Allred



Title: Sr. Operations Assistant

Date: 08/03/2005

(This space for state use only)

RECEIVED

AUG 11 2005